

2 070203

10-31

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 095-21,139 - 0000
NE, SEC. 19, T 29 S, R 6 W/4E
feet from N/S section line
feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5348

Lease Name Osborn Well # 1

Operator: Robert E. Campbell
Name & Address: 2600 N. Rock Road, #110
Wichita, KS 67206

County Kingman 34.97
Well Total Depth 4153 feet
Conductor Pipe: Size feet
Surface Casing: Size 8-5/8 feet 240

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Pratt Well Service License Number 5893

Address P. O. Box 847 Pratt, KS 67124

Company to plug at: Hour: 10:00 Day: 31 Month: 10 Year: 19 89

Plugging proposal received from Warren Richardson

(company name) (phone) 316-775-3613

were: Sand bottom to 4060' & 5 sx common - 75' plug at 1100' - 75' plug
at 600' - 300' to surface

RECEIVED
COMMISSION

11-16-89 NOV 16 1989

CONSERVATION DIVISION
Wichita, Kansas

Plugging Proposal Received by Doug Louis
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 4:00 Day: 31 Month: 10 Year: 19 89

ACTUAL PLUGGING REPORT Sanded bottom to 4060' & 5 sx common - shot casing 4-1/2"
at 1488' - pulled to 1100' & pumped 75' plug - pulled to 600' & pumped at 75'
plug - pulled to 300' & pumped to surface 60/40 6%

Remarks: Halliburton #851370
(If additional description is necessary, use BACK of this form.)

Signed *[Signature]*
(TECHNICIAN)

INVOICED

GATE 11-17-89
INV. NO. 26499