

2040127

API NUMBER 15-095-204570000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION NE/NE/SE, SEC. 18, T. 29 S, R. 6 E
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

2310 feet from N/O section line

330 feet from W/O section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5348

Lease Name Albrecht Well # 1

Operator: Robert E. Campbell

County Kingman 137.09

Name & Address 260 N. Rock Road.

Well Total Depth 4218 feet

Wichita KS 67206

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 216

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casings License Number 6050

Address Box 176 Chase KS.

Company to plug at: Hour: _____ Day: _____ Month: _____ Year: 19 _____

Plugging proposal received from Norman Voth

(company name) Kelso Casings (phone) _____

were: 5 1/2 3500' Sand Back to 3280 w/ 6 ex

PBTD 3438

3H, 6G, 115 sx 60/40 3% 2%

Perf 3330-34

ACW

RECEIVED
CONSERVATION DIVISION
WICHITA, KANSAS

NOV 15 11-16-84

Plugging Proposal Received by Don Thompson (TECHNICIAN)

Operations attended by Agent?: All _____ Part None _____

Operations Completed: Hour: 1300 Day: 7 Month: 11 Year: 19 84

ACTUAL PLUGGING REPORT The Bottom was sanded back to 3280'

and 6 sacks of cement was spotted on top of sand plug.

The pipe was pulled from the well and 2701' of

5 1/2 was recovered. The top was plugged by

pumping 3 sacks of hulls, 6 sacks of gel and 115

sacks of 60/40 RZ MIX Cement 2% sel 3% cc by

Remarks: Allied Cementing # 39067

(if additional description is necessary, use BACK of this form.)

INVOICED (did not) observe this plugging.

DATE 11-20-84

W

Signed Steve Anderson (TECHNICIAN)

RO

INV. NO. 4877