

6 041310

7-13
API NUMBER 15-063-21,396 *00-0199 R*

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

S/2 S/2 SW SEC. 17, T 15 S, R 27 E
330 feet from S section line
3960 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9067

Lease Name G. Coberly Well # 2

Operator: DaMar Resources, Inc.
Name & Address: P.O. Box 70
Hays, Kansas 67601

County Gove 137.15

Well Total Depth 4220' feet

Conductor Pipe: Size 13 3/8 feet 104.6'

Surface Casing: Size 8 5/8 feet 345' w/165 sx. cement.

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Abercrombie RTD., Inc. License Number 30684

Address Wichita, Kansas 67202

Company to plug at: Hour: 1:15 P.M. Day: 13 Month: 7 Year: 19 91

Plugging proposal received from Mr. Tony Martin

(company name) _____ (phone) _____

were: Ordered 215 sx. 60/40 poz. - 6% gel. w/1/4# flocele.

Spot all plugs through drill pipe and displace all cement plugs with heavy mud.

Plugging Proposal Received by Dennis L. Hamel
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 1:15 PM Day: 13 Month: 7 Year: 19 91

ACTUAL PLUGGING REPORT Spot 25 sx. @ 1850'.

Spot 100 sx. @ 775'.

Spot 40 sx. @ 375'.

Spot 10 sx. @ 40'.

40 sx. in rathole.

RECEIVED
STATE CORPORATION COMMISSION
JUL 22 1991
CONSERVATION DIVISION
Wichita, Kansas

Remarks: Anhy. 1839' - 77'. Elev. 2377'.

(If additional description is necessary, use BACK of this form.)

INVOICED
(I did not) observe this plugging.

DATE 8-12-91

INV. NO. 32670

J. S.

Signed *Dennis L. Hamel*
(TECHNICIAN)