

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 9482

Operator: National Petroleum Rs., Inc.  
Name & Address 260 N. Rock Road  
Wichita, Ks. 67206

2-11 110  
API NUMBER 15-063.21242.00.00

SW, SEC. 29, T. 15 S, R. 26 W&E  
2310 feet from S section line  
4900 feet from E section line

Lease Name Jasper A Well # 1  
County Gove 139.43

Well Total Depth 4290 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 346 w/200 sk

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A   
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Lobo Drilling License Number \_\_\_\_\_

Address Wichita, Ks.

Company to plug at: Hour: 3:30AM Day: 11 Month: Feb Year: 19 89

Plugging proposal received from Irvin Neighbors

(company name) Lobo Drilling (phone) \_\_\_\_\_

were: Order 180 sks 60/40 Poz 6% Gel 3% Cal Cl 1 sk F.C. and 8 5/8" plug.

Spot with drill pipe with no less than 36 vis. mud between all plugs with good circulation and no fluid loss.

RECEIVED  
STATE CORPORATION COMMISSION

2-27-89

Plugging Proposal Received by Gilbert G. Scheck  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ None

Operations Completed: Hour: 3:30 AM Day: 11 Month: Feb Year: 19 89

ACTUAL PLUGGING REPORT  
1st plug at 2000' w/20 sks  
2nd plug at 950' w/100 sks 1 sk F.C.  
3rd plug at 400' w/40 sks  
4th plug at 40' w/10 sks  
10 sks in rathole

Remarks: Halliburton Cement  
(If additional description is necessary, use BACK of this form.)

~~operator~~ did not observe this plugging.

Signed Gilbert G. Scheck  
(TECHNICIAN)  
Gilbert G. Scheck

INVOICED  
DATE 3-1-89  
SERIAL NO. 24012