

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-083-21,264-0000

LEASE NAME Fagen

WELL NUMBER 1

SPOT LOCATION C N/2 NE NW

SEC. 16 TWP. 24S RGE. 23 (E) or (W)

COUNTY Hodgeman

Date Well Completed 11-16-86

Plugging Commenced 11-16-86

Plugging Completed 11-16-86

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Viking Resources

ADDRESS 217 E. William, Wichita, Kansas 67202

PHONE # (316) 262-2502 OPERATORS LICENSE NO. 5011

Character of Well D & A  
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? District #1

Is ACO-1 filed? No If not, is well log attached? Yes

Producing formation N/A Depth to top \_\_\_\_\_ bottom \_\_\_\_\_ T.D. 4720

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	259'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

Spotted 40 sx cement @ 1580' thru drill pipe

Spotted 50 sx cement @ 750' thru drill pipe

Spotted 50 sx cement @ 290' thru drill pipe

Spotted 10 sx cement @ 40' thru drill pipe

Spotted 15 sx cement in rathole

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor White & Ellis Drilling, Inc. License No. 5420  
Address 401 East Douglas, Suite 500, Wichita, Ks. 67202


STATE OF Kansas COUNTY OF Sedgwick, ss.

Ernest Sifford (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God. NOV 24 1986

(Signature) Ernest Sifford


(Address) 401 E. Douglas, Suite 500  
Wichita, Ks. 67202

SUBSCRIBED AND SWORN TO before me this 20th day of November, 1986



David F. Jamis  
Notary Public

My Commission expires: 6-10-87



# WHITE

AND ELLIS DRILLING, Inc.

## DRILLERS LOG

OPERATOR: Viking Resources  
217 E. William  
Wichita, KS 67202

CONTRACTOR: White & Ellis Drilling, Inc., 401 E. Douglas, Suite 500,  
Wichita, Ks. 67202

Lease Name Fagen Well No. 1

Sec. 16 T. 24S R. 23W Spot N/2 NE NW

County Hodgeman State Kansas Elevation \_\_\_\_\_

### Casing Record:

Surface: 8 5/8 @ 259' with 165 2<sup>3</sup>/<sub>4</sub> cc gel 3<sup>3</sup>/<sub>4</sub> cc sx.

Production: \_\_\_\_\_ @ \_\_\_\_\_ with \_\_\_\_\_ sx.

Type Well: D & a Total Depth 4720'

Drilling Commenced 11-10-86 Drilling Completed 11-16-86

Formation	From	To	Tops
Cellar	0	7	
Clay, Sand	7	810	
Shale, Shells	810	1850	
Shale, Lime	1850	2670	
Lime, Shale	2670	4590	
Lime	4590	4720	

(NOV 24 1986)