

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

WELL PLUGGING RECORD

Reno County, Sec. 36 Twp. 23 Rge. (E) 4 (W)

Location as "NE/CNW/SW" or footage from lines C W/2 NE

Lease Owner Okmar Oil Company - R.L. Evans

Lease Name Evans Well No. 5 W

Office Address 1130 Vickers KSB&T Building, Wichita, Kansas 67202

Character of Well (completed as Oil, Gas or Dry Hole) Injection Well

Date well completed March 1 19 65

Application for plugging filed May 19 19 70

Application for plugging approved May 20 19 70

Plugging commenced July 18 19 70

Plugging completed July 18 19 70

Reason for abandonment of well or producing formation

Dropped tubing in hole - well junked

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert J. Toman

Producing formation Mississippi Chat Depth to top 3309 Bottom 3388 Total Depth of Well 3388 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION        | CONTENT | FROM | TO   | SIZE   | PUT IN | PULLED OUT |
|------------------|---------|------|------|--------|--------|------------|
| Mississippi Chat | Oil     | 3309 | 3388 | 10 3/4 | 210    | 0          |
|                  |         |      |      | 5 1/2  | 3387   | 0          |
|                  |         |      |      |        |        |            |
|                  |         |      |      |        |        |            |
|                  |         |      |      |        |        |            |
|                  |         |      |      |        |        |            |
|                  |         |      |      |        |        |            |
|                  |         |      |      |        |        |            |
|                  |         |      |      |        |        |            |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Pump 25 sacks Gel and 100 sacks of cement down 5 1/2" casing and pressure up until squeezed. Pump 50 sacks of cement down annulus between 5 1/2" and 10 3/4", pressure up until squeezed. Calculated cement plug in 5 1/2" csg. surface to 860', plug between 5 1/2" and 10 3/4" from surface to 128'.

RECEIVED  
STATE CORPORATION COMMISSION  
AUG 12 1970  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Okmar Oil Company

Address 1130 Vickers KSB&T Building, Wichita, Kansas 67202

STATE OF KANSAS, COUNTY OF SEDGWICK, ss. Jim Thatcher (employee of owner) or (owner or operator) of the above-described


well being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Jim Thatcher

1130 Vickers KSB&T Bldg., Wichita, Ks. 67202

(Address)

Subscribed and Sworn to before me this 11 day of August, 19 70



Sandra L. Mendoza Notary Public

My commission expires June 17, 1973

# UNITED CEMENTING & ACID CO., INC.

FIELD TICKET NO. 3249

INVOICE NO. 4058

DATE 7-21-70

PHONE DA 1-4680

REMIT TO  
BOX 1214  
EL DORADO, KANSAS 67042

Harold Wilburn  
3803 Panorama Rd.  
Hutchinson, Kansas

FULLY INSURED

15-155-30015-0000

| DATE OF JOB                                     | COUNTY                             | STATE        | LEASE        | WELL NO.        |
|---|------------------------------------|--------------|--------------|-----------------|
| 7-18-70   | Reno                               | Ks.          | Evans & Base | SVD             |
| SIZE CASING                                     | DEPTH OF WELL                      | DEPTH OF JOB | PLUG DEPTH   | PRESSURE        |
| Cementing Surface Pipe                          |                                    |              |              | \$              |
| Cementing Production String PLUGGING TO ABANDON |                                    |              |              | \$ 175.00       |
| 150   | Saks 50/50 PozMix Cement           |              | @ 1.00       | 150.00          |
| 25  | Saks Gel                           |              |              | 125.00          |
|   | Bulk Service Chg. on cement        |              | @ .35        | 52.50           |
|   | Bulk Service Chg. on Gel           |              |              | 2.75            |
|   | Drayage (7.5 ton x 20¢ x 65 miles) |              |              | 97.50           |
| SALES TAX                                       |                                    |              |              | \$ 18.26        |
| \$18.26 Discount--30 Days                       |                                    |              |              | TOTAL \$ 627.01 |

TERMS: NET 30 DAYS  
FROM INVOICE DATE

*Paid  
Aug. 6-1970  
check #394.*

*Less 18.26  
\$ 608.75*

**RECEIVED**  
STATE CORPORATION COMMISSION  
AUG 12 1970  
CONSERVATION DIVISION  
Wichita, Kansas

UNITED CEMENTING & ACID CO., INC.

BOX 1214

EL DORADO, KANSAS 67042

PHONE AC 316-DA 1-4680

DATE 7-19-70 COUNTY Reano.  
 CHG. TO: Harold M. Wilson ADDRESS 3903 Panorama Rd.  
 CITY Fort Tison STATE Kansas ZIP \_\_\_\_\_  
 LEASE & WELL NO. Leans & Luse S.W. SEC. \_\_\_\_\_ TWP. \_\_\_\_\_ RNG. \_\_\_\_\_  
 CONTRACTOR \_\_\_\_\_ TIME ON LOCATION \_\_\_\_\_  
 KIND OF JOB Plugs & Bone  
 SERVICE CHARGE: Leans & Luse Rental

| QUANTITY    | MATERIAL USED              | TYPE    |
|-------------|----------------------------|---------|
| <u>150'</u> | <u>30-50 Payson Cement</u> |         |
| <u>25'</u>  | <u>Rel</u>                 |         |
|             | <u>Drillage on site</u>    |         |
| DEL. CHGE.  | <u>6.5</u>                 | MILEAGE |

RECEIVED BY: \_\_\_\_\_  
 T. D. \_\_\_\_\_ CSG SET AT \_\_\_\_\_ VOLUME \_\_\_\_\_  
 SIZE HOLE \_\_\_\_\_ TBG SET AT \_\_\_\_\_ VOLUME \_\_\_\_\_  
 MAX. PRESS. \_\_\_\_\_ SIZE PIPE \_\_\_\_\_  
 PLUG DEPTH \_\_\_\_\_ PKR DEPTH \_\_\_\_\_  
 PLUG USED \_\_\_\_\_ TIME FINISHED \_\_\_\_\_  
 REMARKS: \_\_\_\_\_  
 \_\_\_\_\_  
 \_\_\_\_\_  
 \_\_\_\_\_  
 \_\_\_\_\_  
 \_\_\_\_\_  
 \_\_\_\_\_  
 \_\_\_\_\_  
 \_\_\_\_\_  
 \_\_\_\_\_

RECEIVED  
 AUG 12 1970  
 STATE CORPORATION COMMISSION  
 CONSERVATION DIVISION  
 Wichita, Kansas

EQUIPMENT USED

| NAME          | UNIT NO.    | NAME          | UNIT NO.   |
|---------------|-------------|---------------|------------|
| <u>Miller</u> | <u>#101</u> | <u>Miller</u> | <u>201</u> |

CEMENTER OR TREATER: \_\_\_\_\_ OWNER'S REP.: Harold M. Wilson

KANSAS GEOLOGICAL SOCIETY  
 KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU  
 KANSAS GEOLOGICAL SOCIETY BUILDING  
 508 EAST MURDOCK - WICHITA, KANSAS

15-155-30015-0000

COMPANY **R. L. Evans & SeRoBee Drilling Co., Inc.**


SEC. **36 23 4W**  
 App. **C W/2 NE**  
 LOC.

FARM **Evans** NO. **5W**

TOTAL DEPTH **3388**  
 COMM. **3-4-65** COMP. **3-17-65**  
 SHOT OR TREATED  
 CONTRACTOR **SeRoBee Drilling Co., Inc.**  
 ISSUED

COUNTY **Reno**

KANSAS



CASING  
 20 10 **3/4 @ 215 W/215 sx**  
 15 B  
 12 6  
 13 5 **1/2 @ 3387 W/100 sx**

ELEVATION **1461 KB**

PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATIONS

|             |                   |
|-------------|-------------------|
| 0 - 210     | Shale & Lime      |
| 210 - 250   | Blue Shale        |
| 250 - 525   | Shale & Anhydrite |
| 525 - 2539  | Lime & Shale      |
| 2539 - 2882 | K. C. Lime        |
| 2882 - 3085 | Lime              |
| 3085 - 3279 | Lime & Shale      |
| 3279 - 3318 | Lime              |
| 3318 - 3363 | Miss. Lime        |
| 3363 - 3388 | Lime              |

RECEIVED  
 STATE CORPORATION COMMISSION  
 MAY 20 1970  
 CONSERVATION DIVISION  
 Wichita, Kansas