

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Dorby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

15-155 30803-0000

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

API NUMBER 126-64

LEASE NAME McElwain

WELL NUMBER 2

NE NW 3E
 Ft. from S Section Line

Ft. from E Section Line

SEC. 36 TWP. 23S RGE. 4W (E) or (W)

COUNTY Reno

Date Well Completed 12-6-64

Plugging Commenced 7-6-90

Plugging Completed 8-9-90

LEASE OPERATOR S & K Oil Co

ADDRESS RI Box 99 Burton KS 67020

PHONE # (316) 463-5741 OPERATORS LICENSE NO. 5271

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC District Office prior to plugging this well? yes

Which KCC Office did you notify? Dist # 2

Is ACO-1 filed? yes If not, is well log attached?

Producing Formation Miss Depth to Top 9900 Bottom 9930 T.D. 3330

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				<u>10 7/8</u>	<u>252</u>	<u>0</u>
				<u>5 1/2</u>	<u>3300</u>	<u>607'</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

3330 to 3250' sand dumped 6 5/8" cement shot pipe off 607'
Ran tubing 355' 470' 350' to surface & cement

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Gressel Oil Field Serv. Inc. License No. 3004

Address Box 607 Burton KS 67020

STATE OF Ks COUNTY OF Harvey, ss. 9-4-90


Ed Gressel

(Employee of Operator or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Ed Gressel

(Address) Box 607 Burton KS 67020



AND SWORN TO before me this 31st day of August, 19 90

Debra K Hill Johnson
 Notary Public

My Commission Expires: March 31, 1991

S & K OIL CO.
P. O. BOX 682 TULSA, OKLAHOMA
ZIP 74101

COMPLETION REPORT

15-155-30003-0000

Company: S & K Oil Co.
Farm & Well: McElwain #2
Location: NE NW SE Sec. 36-23S-4W
Reno County, Kansas

Commenced: 11-15-64
Completed: 12-6-64
I.P.:

Elev: 1458' KB
RTD: 3301'
CTTD: 3335'

Casing Record:

10 3/4" @ 252' w/240 sx
5 1/2" @ 3300' w/150 sx

Formation Tops: Brown Limestone 2496'
Lansing 2526'
Base of Kansas City 2981'
Cherokee 3151'
Mississippi 3267'

<u>Log:</u>	0	259	Sand & Shale
	259	1235	Shale & Lime
	1235	1980	Shale
	1980	2527	Lime & Shale
	2527	2983	Lime
	2983	3143	Lime & Shale
	3143	3267	Shale
	3267	3335	Chert


Electric Logs: Gamma Ray-Neutron (Great Guns)

DST: None


Cores: None

State of Oklahoma)
County of Tulsa) ss

I, Louis Kahan, Operator, being first duly sworn under oath say: That I have knowledge of the facts, statements, and matters herein contained of the above described well as filed and that the same are true and correct.


LOUIS KAHAN

Subscribed and sworn to before me this 26th day of January, 1965.


NOTARY PUBLIC

My commission expires May 20, 1966.

MAY 01 1966
Wichita, Kansas