

STATE OF KANSAS
STATE CORPORATION COMMISSION
~~200 Colorado Derby Building~~
Wichita, Kansas 67202
130 S. Market - Room 2078

WELL PLUGGING RECORD
K.A.R.-82-3-117

Received
10/4/03

API NUMBER 15-155-03164-0000

LEASE NAME Smith

WELL NUMBER 3

 Ft. from S Section Line

 Ft. from E Section Line

SEC. 36 TWP. 23S RGE. 4 (E) or (W)

COUNTY Reno

Date Well Completed 11/28/64

Plugging Commenced 08/18/03

Plugging Completed 08/19/03

RECEIVED

AUG 25 2003

KCC WICHITA

NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Kahan & Associates, Inc.

ADDRESS P.O. Box 700780 Tulsa, OK 74170-0780

PHONE# (918) 492-9797 OPERATORS LICENSE NO. 4252

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 08/13/03 (verbal) (date)

by Dave Wertz (KCC District Agent's Name).

Is ACO-1 filed? yes If not, is well log attached? sent w/ application

Producing Formation Mississippian Depth to Top 3266' Bottom 3302' T.D. 3338'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Mississippian	Oil	0	260	10 3/4"	260'	-
		0	3302	5 1/2"	3302'	-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Dump 5 sx cement on top of fill @ 3020'. Perforate w/ 4 shots @ 600'. Run tbg and spot 35 sx 60/40 Poz @ 610'. Run 1" tbg down casing annulus to 310' and circulate cement to surface. 158 sx used. Run tbg inside casing and tag plug @ 400'. Spot tbg @ 310' and fill casing to surface w/ 49 sx 60/40 Poz cement. (Witnessed by Mike Wilson KCC)
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Scott's Well Service, Inc. License No. 6819

Address Box 136 Roxbury, KS 67476

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Kahan & Associates, Inc.

STATE OF Oklahoma COUNTY OF Tulsa, ss.

David M. Wilson Operations Manager (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.


(Signature) David M. Wilson

(Address) P.O. Box 700780 Tulsa, OK 74170-0780

SUBSCRIBED AND SWORN TO before me this 22nd day of August, 2003

Virginia L. Freese
Notary Public

My Commission Expires: Nov. 29, 2003



99018580