

STATE OF KANSAS  
 STATE CORPORATION COMMISSION  
 200 Colorado Derby Building  
 Wichita, Kansas. 67202

WELL PLUGGING RECORD  
 K.A.R.-82-3-117

15-55-02845-0000  
 Dr. 19. Completion

API NUMBER 1-23-34  
 LEASE NAME Maggie Stalcup  
 WELL NUMBER 1  
760 Ft. from N Section Line  
660 Ft. from W Section Line  
 SEC. 36 TWP. 23S RGE. 4 (E) or (W)  
 COUNTY Renov

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

LEASE OPERATOR ARCO Oil & Gas Co.  
 ADDRESS Box 849 Gl Bend Kan. 67530  
 PHONE#(316) 793-5467 OPERATORS LICENSE NO. 5398

Date Well Completed 1-23-34  
 Plugging Commenced 12-17-86  
 Plugging Completed 12-18-86

Character of Well Oil  
 (Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes  
 Which KCC/KDHE Joint Office did you notify? Dist # 2 Wichita  
 Is ACO-1 filed? No If not, is well log attached? No logs Run

Producing Formation Miss. Chat Depth to Top 3262 Bottom 3373 T.D. 3373  
 Show depth and thickness of all water, oil and gas formations. P.BTD 3328

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				15 1/2	239	None
				12 1/2	469	None
Miss. chat				8 1/4	3291	520'


Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.  
REH w/ 2 1/8 Tbg. To 3290' mix & Pump 100SX comm. w/ 1/4" Flusent Per SX. POH w/ Tbg. Cut 8 1/4" csg  
off. REH w/ 2 1/8 Tbg To 520' inside 12 1/2" csg. Mix 460# Halls & 425 SA 6940 Poz w/ 4" gel &  
3 1/2" C.C. Cir cmt to surface. SDFN. Cir cmt on 12 1/2" csg. Found cmt down to 214' REH w/ Tbg. mix  
170SX 6940 Poz w/ 2 1/2" gel & 3 1/2" CC Cir cmt to surface. POH w/ Tbg. SDFN. CK cmt in 12 1/2"  
 (If additional description is necessary, use BACK of this form.) TURN TO BACK side

Name of Plugging Contractor KIZZAR Well Service License No. 07868  
 Address Box 346 Chase KS.  
 STATE OF KANSAS COUNTY OF Rice, ss.

STATE CORPORATION COMMISSION  
 DEC 24 1986  
 12-24-86  
 CONSERVATION DIVISION  
 Kansas

Richard Tennant (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Richard Tennant  
 (Address) Box 849 Gl. Bend KS.



SUBSCRIBED AND SWORN TO before me this \_\_\_\_\_ day of \_\_\_\_\_, 19 \_\_\_\_\_

Mary M. Guenier  
 Notary Public  
 My Commission Expires: June 26, 1990

CSG. Found cmt 1' Down. Well PVA 2:00 P.M. 12-18-86  
Final Report Witnessed by KCC. JOHN SANDERS

12-18-86  
KCC