

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas


15-095-01218-0000

WELL PLUGGING RECORD

Kingman County. Sec. 23 Twp. 29S Rge. 7W (E) (W)

Location as "NE/CNW/SW" or footage from lines SW NE NE
Lease Owner O. A. Sutton
Lease Name Lecklider Well No. 2
Office Address 407 Ins. Bldg., Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed July 20 1961
Application for plugging filed July 20 1961
Application for plugging approved July 20 1961
Plugging commenced July 20 1961
Plugging completed July 20 1961
Reason for abandonment of well or producing formation _____

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Frank Broadfoot
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4270 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				252' of	10-3/4"	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled with mud to 240', set plug #1 at 240' with 4 sacks of hulls and 30 sacks of cement. Set plug #2 at 35' with 1/4 sacks hulls and 15 sacks cement. Plugged at 4:30 p.m. July 20, 1961.

RECEIVED
STATE CORPORATION COMMISSION

JUL 26 1961 07-26-61

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor J. S. Sutton Drilling Co.
Address 313 Ins. Building, Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
D. G. Comstock (employee of owner) or owner or sponsor of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) D. G. Comstock
D. G. Comstock

Subscribed and sworn to before me this 25th day of July, 1961

My commission expires Feb. 5, 1964

(Address) Sara Wimberly
Sara Wimberly
Sara Wimberly Notary Public.

Lecklider #2, O. A. Sutton
 SW NE NE Section 23-29S-7W
 Kingman County, Kansas

Date Commenced - July 6, 1961
 Date Completed - July 20, 1961
 Elevation - 1577 K.B.
 Casing - 252' of 10-3/4" casing with 200 sacks of HA5 Cement.
 Completed at 3:30 a.m. on July 7, 1961.

DRILLERS LOG

252 - 313	Red Bed
313 - 963	Red Bed
963 - 1080	Shale/Red Bed
1230 - 1395	Lime/Shale
1395 - 1525	Lime/Shale
1525 - 1640	Lime/Shale
1640 - 1747	Lime
1747 - 1840	Lime
1840 - 1960	Lime
1960 - 2060	Lime/Shale
2060 - 2205	Shale/Lime
2205 - 2410	Shale/Lime
2410 - 2505	Lime/Shale
2505 - 2680	Shale/Lime
2680 - 2840	Shale/Lime
2840 - 2925	Shale/Lime
2925 - 3058	Shale/Lime
3058 - 3173	Lime/Shale
3173 - 3315	Lime/Shale
3315 - 3430	Lime
3430 - 3493	Lime
3493 - 3544	Lime
3544 - 3605	Lime
3605 - 3685	Lime
3685 - 3725	Lime
3735 - 3746	Lime
3746 - 3780	Lime (K.C.)
3780 - 3786	Lime
3786 - 3793	Lime
3793 - 3845	Lime (K.C.)
3845 - 3910	Lime
3910 - 3940	Lime
3940 - 3955	Lime/Shale
3955 - 4070	Lime/Shale
4070 - 4118	Lime/Shale
4118 - 4133	Lime
4133 - 4135	Miss.
4135 - 4190	Miss.
4190 - 4230	Miss.
4230 - 4245	Miss.
4245 - 4270	Miss.
4270 -	Total Depth (T.D.)

RECEIVED
 STATE CORPORATION COMMISSION
 JUL 26 1961
 CONSERVATION DIVISION
 Wichita, Kansas

STATE OF KANSAS)
) ss
 SEDGWICK COUNTY)

I, the undersigned, being duly sworn on oath, state that the above Drillers Log is true and correct to the best of my knowledge and belief and according to the records of this office.

J. S. SUTTON DRILLING COMPANY

By James S. Sutton

Subscribed and sworn to before me this 24th day of July, 1961

My Commission expires February 27, 1965

By Henry D. Ficker
 Notary Public