

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

Rice County. Sec. 23 Twp. 20 Rge. 9 (E) W (W)

Location as "NE/CNW/SW" or footage from lines. SW SE NW

Lease Owner Clinton Oil Company

Lease Name Rolfs Well No. 3

Office Address Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Oil

Date well completed November 18 19 62

Application for plugging filed July 7 19 66

Application for plugging approved July 8 19 66


Plugging commenced 7-26-66 19

Plugging completed 7-27-66 19

Reason for abandonment of well or producing formation Depleted.

If a producing well is abandoned, date of last production July 5 19 66

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Gilbert Toman

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3384 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				10-3/4"	194'	None
				5-1/2"	3383'	2470'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Checked hole to 3384', sanded hole to 3370' and dumped 5 sacks of cement @ 3370' with dump bailer. Pulled 5 1/2" casing, set rock bridge from 200' to 190' and dumped 25 sacks of cement. Mudded hole to 30', set rock bridge to 20' and ran 10 sacks of cement to base of cellar.

RECEIVED
STATE CORPORATION COMMISSION

PLUGGING COMPLETE.

AUG 4 1966 08-04-66

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor KNIGHT CASING PULLING COMPANY

Address CHASE, KANSAS

STATE OF KANSAS COUNTY OF RICE, ss.

Noel J. Knight (employee of owner) or ~~former operator~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

Noel J. Knight

Chase, Kansas

(Address)

SUBSCRIBED AND SWORN to before me this 29th day of July, 1966

Milton J. Volin

Notary Public.

My commission expires May 20, 1968

RAYMOND OIL COMPANY, INC.
 No. 3 ROLFS
 SW SE NW 23-20S-9W
 Rice County, Kansas

ELEVATION: 1675 DF
 1679 KB

Contractor: Raymond Drilling Company - Rig #7
 Commenced: November 10, 1962
 Completed: November 18, 1962

Casing Record:
 5½" @ 3379 1/2' w/150 Sx.

Figures Indicate Bottom of Formation

<u>Formation</u>	<u>Depth</u>
Sand and Clay	123
Redbed	265
Anhydrite	270
Redbed and Shale	1100
Lime and Shale	1618
Shale and Lime	1900
Lime and Shale	2210
Shale and Lime	2388
Lime	2585
Lime and Shale	2860
Lime	3342
Sand	3355
Lime	3377
Sand - Arbuckle	3381 TD


TOPS

Heebner	2731
Brown Limestone	2866
Lansing-Kansas City Groups of Ist.	2898
Base Kansas City Group	3194
Maquoketa Limestone & Chert	3235
Viola Limestone	3277
Simpson Shale	3323
Arbuckle dolomite	3378
Rotary Total Depth	3381

RECEIVED
 STATE CORPORATION COMMISSION
 JUL 8 1966
 CONSERVATION DIVISION
 WICHITA, KANSAS

STATE OF KANSAS)
) SS.
 COUNTY OF SEDGWICK)

I hereby certify the above to be true and correct to the best of my knowledge.


 Patrick R. Raymond, Vice-President

Subscribed and sworn to before me this 17th day of December, 1962.


 Barbara A. Kennedy, Notary Public

My commission expires July 9, 1966.