


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Kingman County, Sec. 32 Twp. 29 Rge. 7 (E) (W) X



Locate well correctly on above Section Plat

Location as "NE/CNW/SW" or footage from lines SW SE NE
Lease Owner Pickrell Drilling Company
Lease Name Brand Well No. 2
Office Address 705 Fourth National Bank Building Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole)
Date well completed 19
Application for plugging filed 1-11-64 19
Application for plugging approved 1-15-64 19
Plugging commenced 1-17-64 19
Plugging completed 1-18-64 19
Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Archie V. Elving
Producing formation Depth to top Bottom Total Depth of Well 4269 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	239	None
				5 1/2	None	3239

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Cleaning out cellar. Measured Total Depth. Sanded to 4170' and 5 sacks of cement. Rigged up unit and jacks. Working pipe. Shot well at 3224'...
Working pipe. Pulling pipe...
Pulling pipe. Plugging well at 275'. Build 18' rock bridge and 20 sacks of cement. Mudded to 40'. Build 10' rock bridge and 10 sacks of cement.

RECEIVED
STATE CORPORATION COMMISSION

JAN 23 1964

01-23-64

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Forbes Casing Pulling, Inc.
Address P. O. Box 221 Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
J. O. Forbes (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. O. Forbes
P. O. Box 221 Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 21 day of January 1964

My commission expires May 27, 1964

Notary Public.

ROTARY DRILLING LOG

COMPANY: Pickrell Drilling Company
 705 Fourth National Bank Building
 Wichita, Kansas

LOCATION: Brand #2, SW SE NE, Sec. 32-29S-7W,
 Kingman County, Kansas

Rotary Drilling Commenced 12-14-60
 Rotary Drilling Completed 12-29-60

CONTRACTOR: **PICKRELL DRILLING COMPANY**
 Wichita, Kansas

CASING RECORD: Ran 6 jts. 22.7# 8 5/8" Spiralweld Casing. Set @ 239' w/165 sks. Circ.
 Ran 134 jts. 5 1/2" casing. Set @ 4268' w/150 sks.

LOG

(Figures indicate bottom of formation — measurements from top of rotary bushing.)

240	Red rock	<u>Circulate for Samples</u>
1110	Red rock, shale	
1370	Shale, lime	4150
1805	Lime	4160
2990	Lime, shale	4182
3092	Lime	4188
3415	Lime, shale	4195
3903	Lime	4200
4150	Lime, shale	4205
4270	Miss. T.D.	4215
		4225
		4230
		4240
		4270

Slope Test

1500 - 0°
 2000 - 0°
 3092 - 0°
 4250 - 0°

S.L.M.

1000 - OK
 2000 - OK
 3000 - OK
 4000 - OK

RECEIVED
 STATE CORPORATION COMMISSION
 JAN 15 1964
 CONSERVATION DIVISION
 Wichita, Kansas

The undersigned, C. W. Sebitts, Attorney-in-Fact for PICKRELL DRILLING COMPANY, hereby certifies in behalf of said Company, that the above is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

PICKRELL DRILLING COMPANY

By [Signature]
 Attorney-in-Fact

STATE OF KANSAS
 COUNTY OF SEDGWICK } ss.:

On the 14th day of December, 1960, before me the undersigned, a Notary Public, in and for

the County of Sedgwick aforesaid, personally appeared C. W. Sebitts, to me known to be the identical person who subscribed the name of PICKRELL DRILLING COMPANY to the foregoing instrument as its Attorney-in-Fact and acknowledged to me that he executed the same as his free and voluntary act and deed, and as the free and voluntary act and deed of such company, for the uses and purposes therein set forth.

Witness my hand and seal of office the day and year last above written.

My commission expires: March 7, 1964

[Signature]
 Notary Public
 Marilyn A. Davis