

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

15-095-21565-0000  
API NUMBER Drilling completed

LEASE NAME 2-8-87 Brand

WELL NUMBER 1-32

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

           Ft. from S Section Line

           Ft. from E Section Line

C-NW-SE  
SEC. 32 TWP. 29S RGE. 7 W (E) or (W)

LEASE OPERATOR Pratt Well Service, Inc.

ADDRESS Box 847 Pratt, Kansas 67124

COUNTY Kingman

PHONE# (316) 672-2531 OPERATORS LICENSE NO. 5893

Date Well Completed 2-8-87

Character of Well Oil

Plugging Commenced 7-12-88

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 7-15-88

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Wichita, Kansas

Is ACO-1 filed? yes If not, is well log attached?           

Producing Formation            Depth to Top            Bottom            T.D. 4285'

Perfs: 4210-16 4183-89 4168-73 4160-63

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
		0	214.50	8 5/8"	214.5	0
		214.5	4281	5 1/2"	4066.5	2591' 64 jts.

Describe in detail manner in which the well was plugged, indicating where the mud fluid was placed and the methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from        feet to        feet each set.

Sanded back to 3992', dumped 5 sx. cement. Shot at 3385-3046-2836 and 2591, recovered 64 jts. 7-15-88; Pumped 3 sx. hulls, 12 sx. gel, 100 sx. cement, 60-40 poz. 4% gel. 500# max. 250# ISIP.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Pratt Well Service, Inc. License No. 5893

Address P.O. Box 847 Pratt, Kansas 67124


STATE OF Kansas COUNTY OF Pratt, ss.

Judy Berry plugging contractor (Employee of ~~operator~~) or (~~operator~~) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Judy Berry

(Address) Box 847 - Pratt, Ks.



SUBSCRIBED AND SWORN TO before me this 27<sup>th</sup> day of July, 19 88

Dorothy L. Ferguson  
Notary Public

My Commission Expires: February 06, 1989