

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH

Locate well correctly on above
Section Plat

Kingman County. Sec. 33 Twp. 29 Rge. 7W (E) (W)
Location as "NE/CNW%SW%" or footage from lines NW NW SE
Lease Owner Rupp-Ferguson Oil Company
Lease Name Campbell "C" Well No. 1
Office Address 522 Union Center Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) DRY HOLE
Date well completed 19
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced 19
Plugging completed April 13 19 60
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well Fred W. Hampel
Producing formation Depth to top Bottom Total Depth of Well 4280' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

T. D. 4280' - S. P. 8 5/8"- 243 C W C
Heavy mud to 240' set plug used 1/4 sack of hulls, 18 sacks of cement through drill pipe, mud to 35' set plug used 1/4 sacks hulls, 10 sacks cement to base of cellar.

Bridge rat hole used some hulls, and 2 sacks of cement.

RECEIVED
STATE CORPORATION COMMISSION

08-05-63 AUG 5 1963

CONSERVATION DIVISION
Wichita, Kansas

Name of Plugging Contractor Rupp-Ferguson Oil Co.
Address 522 Union Center, Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
L. Wendell Knox (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) L. Wendell Knox

522 Union Center
(Address)

SUBSCRIBED AND SWORN TO before me this 30 day of July, 19 63

My commission expires May 11, 1967

Marguerite Richey
Notary Public.

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

COPY

Company- RUPP-FERGUSON
Farm- Campbell "C" No. 1

SEC. 33 T. 29 R. 7W
NW NW SE

Total Depth. 4280'
Comm. 4-2-60


Comp. 4-13-60

County Kingman
KANSAS

Shot or Treated.

Contractor.

Issued. 6-11-60



CASING:
8 5/8" 243' cem. w/160 sx.

Elevation. 1511 DF

Production. Dry

Figures Indicate Bottom of Formations.

red sand	6
red rock	50
red bed	515
shale & salt	933
anhydrite strks.	1014
shale	1089
anhydrite	1116
shale & shells	1190
lime & shale	1933
shale	2403
shale & lime	3157
shale & sand	3360
shale, sandy lime & lime	3491
lime & shale	3667
lime	3832
lime & shale	3885
lime	4011
lime & shale	4069
Mississippian	4280
Total Depth	

TOPS: SCOUT
Mississippi 4126

RECEIVED
STATE CORPORATION COMMISSION

APR 5 1966

MINERAL RIGHTS DIVISION
Wichita, Kansas