

API NUMBER Drilled 1960 0000

LEASE NAME Campbell

WELL NUMBER A-2

 Ft. from S Section Line

 Ft. from E Section Line

SEC. 33 TWP. 29 RGE. 7 (E) or (W)

COUNTY Kingman

Date Well Completed

Plugging Commenced 12-28-93

Plugging Completed 12-30-93

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Graham-Michaelis Corp.

ADDRESS P. O. Box 769 Woodward, OK 73801

PHONE# (405) 256-6491 OPERATORS LICENSE NO. 5134

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on (date)

by Steve Van Gieson (KCC District Agent's Name).

Is ACO-1 filed? If not, is well log attached?

Producing Formation Depth to Top Bottom T.D. 4255'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8	245'	none.
				5 1/2	4253'	3027'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Sanded bottom to 4114' & 5 sks cement. Shot @ 3200 & 3027, came loose. Pulled to 1150, pumped 35 sks cement. Pulled to 700, pumped 35 sks cement. Pulled to 295 & circulated 85 sks cement to surface. Pulled rest of pipe & topped off w/20 sks cement. 60/40 pos 4% gel. Plugging complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor KELSO CASING PULLING, INC. License No. 6050

Address P. O. BOX 347 CHASE, KS. 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Graham-Michaelis Corp.

STATE OF KANSAS COUNTY OF RICE, ss.

R. DARRELL KELSO (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.


(Signature) R. Darrell Kelso

(Address) P. O. BOX 347 CHASE, KS. 67524

SUBSCRIBED AND SWORN TO before me this 31st day of December, 1993

Irene Herzberg
 Notary Public

My Commission Expires:



01-07-94

CONTRACTOR'S WELL LOG

Rupp-Ferguson No. 2 Fern Campbell
SE NW NW Sec. 33-298-7W
Kingman County, Kansas

Contractor: Rupp-Ferguson Oil Co.
Commenced: 4-14-60
Completed 4-27-60

Elevation 1511 K.B.
1508 D.F.
Set 8 5/8" @ 245' w/150 sacks cement

Figures Indicate Bottom of Formation


90	red rock
245	red shale and rock
365	shale
760	red bed and shale
933	salt and shale
1040	Anhydrite streaks
1088	shale and shells
1516	lime and shale
1600	sand and lime
1617	lime and shale
1753	lime
2498	lime and shale
2720	shale
3257	lime and shale
3414	sandy lime, shale and lime
3584	chalky lime
3853	lime
4126	lime and shale
4255	Mississippian T.D.

STATE OF KANSAS)
) SS:
COUNTY OF SEDGWICK)

I, J. F. Carter, Jr., Petroleum Engineer for Rupp-Ferguson Oil Co.,
hereby certify the above and foregoing to be a true and correct copy of the log of
the No. 2 Fern Campbell well.

J. F. Carter, Jr.
J. F. Carter, Jr.

RECEIVED
STATE CORPORATION COMMISSION
NOV 24 1993
CONSERVATION DIVISION
Wichita, Kansas



Subscribed and sworn to before me this 28th day of April, 1960

My Commission Expires May 11, 1963.

Marguerite Dickey
Marguerite Dickey, Notary Public