

STATE OF KANSAS  
STATE CORPORATION COMMISSION


15-095-20661-0000

WELL PLUGGING RECORD

Give All Information Completely.  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.  
245 North Water  
Wichita, KS 67202

Kingman County, Sec. 33 Twp. 29S Rge. 7W E/W  
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines  
NW NE SE

Lease Owner The Maurice L. Brown Company  
Lease Name Armstrong Well No. 1  
Office Address 200 Sutton Place, Wichita, KS 67202  
Character of Well (Completed as Oil, Gas or Dry Hole)  
Dry Hole



Locate well correctly on above Section Plat

Date Well completed 11/26/77 19  
Application for plugging filed 11/26/77 19  
Application for plugging approved 11/26/77 19  
Plugging commenced 11/26/77 19  
Plugging completed 11/26/77 19  
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Bill Owens  
Producing formation Depth to top Bottom Total Depth of Well  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	Surface	0	247	8 5/8"	Yes	No

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Run plugging stands in hole  
Bottom plug @ 240' with 255 sxs  
Top plug @ 40' to surface with 125 sxs

RECEIVED  
STATE CORPORATION COMMISSION

JAN 26 1978 01-26-78

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Gabbert-Jones, Inc.

STATE OF KANSAS COUNTY OF SEDGWICK, ss.  
Vern Haselhorst (employee of owner) or (owner or operator)  
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Vern Haselhorst  
200 Sutton Place, Wichita, KS 67202  
(Address)

SUBSCRIBED AND SWORN TO before me this 25th day of January, 1978

Kathleen L. Leake Notary Public.

My commission expires 10/1/78



GABBERT-JONES, INC.  
 WICHITA, KANSAS  
 DRILLERS' WELL LOG

Armstrong #1  
 NW NE SE Sec 33-29S-7W  
 Kingman County Kansas

Commenced: 11-12-77

Completed: 11-26-77

OPERATOR: MAURICE L. BROWN

From	Depth to	Formation	Remarks
0	20	Sand	Ran 6 jts of 24# 8 5/8" csg
20	250	Redbed	set @ 247' Cemented w/
250	995	Redbed-Shale	225 sks Class A 3% CC
995	1355	Shale-Shells	1/4# Floseal per sack
1355	1590	Shale-Shells	PD @ 7:15 p.m. 11-12-77
1590	1720	Shale-Lime	
1720	1945	Lime	
1945	2170	Lime-Shale	
2170	2515	Lime	
2515	2745	Shale-Lime	
2745	3025	Lime	
3025	3335	Shale-Lime	DRY & ABANDONED
3335	4268	Lime	
	4268 - TD		

STATE OF KANSAS )  
 ) SS  
 COUNTY OF SEDGWICK)

I, the undersigned, being duly sworn on oath, state that the above Drillers' Well Log is true and correct to the best of my knowledge and belief and according to the records of this office.

GABBERT-JONES, INC.

*James S. Sutton II*  
 JAMES S. SUTTON II

Subscribed and sworn to before me this 1st day of December, 1977.

*Elizabeth J. Edwards*  
 ELIZABETH J. EDWARDS-NOTARY PUBLIC

My Commission expires February, 6, 1979.

