

API NUMBER 12-01-75

15-083-20448-0001

LEASE NAME Clark-Welty

TYPE OR PRINT

WELL NUMBER 1

NOTICE: Fill out completely  
and return to Coas. Div.  
office within 30 days.

3300 Ft. from S Section Line

1980 Ft. from E Section Line

LEASE OPERATOR Kytex, Inc.

SEC. 27 TWP. 22 SRGE. 21 (E) or (W)

ADDRESS 1524 N. 143rd St. East, Wichita, Kansas 67230

COUNTY Hodgeman

PHONE# (316) 733-2465 OPERATORS LICENSE NO. 30975

Date Well Completed 12-01-75

Character of Well Oil

Plugging Commenced 06-01-94

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 06-03-94

The plugging proposal was approved on 06-03-94 (date)

by Case Morris (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? \_\_\_\_\_

Producing Formation Arbuckle Depth to Top 4430 Bottom 4475 T.O. 4475

Show depth and thickness of all water, oil and gas formations:

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
	Surface	0		8 5/8"	307	
	Casing	0		4 1/2"	4555	3139'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set  
Sanded to 50' above perfs.-Bailed in 4 sacks of cement, loaded hole, mixed 50 sacks, @ 1400', 30 sacks @ 550', 50 sacks @ 330'. Pulled casing to 170' and circulated cement to surface with 30 sacks

Name of Plugging Contractor D.S. & W. Well Servicing, Inc. License No. STATE 1609

Address P.O. Box 231, Claflin, Kansas 67525

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: D.S. & W. Well Servicing, Inc.

STATE OF Kansas COUNTY OF Barton, ss.

Arthur P. Strube (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.

(Signature) Arthur P. Strube  
(Address) P.O. Box 231, Claflin, Kansas 67525

SUBSCRIBED AND SWORN TO before me this 07 day of June, 19 94

Karlynn K. Beck  
Notary Public

My Commission Expires: 09-28-94

USE ONLY ONE SIDE OF EACH FORM

