


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Kearny County, Sec. 17 Twp. 26S Rge. (E) 38 (W)
Location as "NE/CNW/SW" or footage from lines. C NE SW
Lease Owner E. E. Fogelson et al
Lease Name H. E. Johnson Well No. 1
Office Address 2010 Republic Bank Building, Dallas, Texas
Character of Well (completed as Oil, Gas or Dry Hole) Dry hole
Date well completed June 5 19 63
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced June 6 19 63
Plugging completed June 6 19 63
Reason for abandonment of well or producing formation Lack of oil or gas shows.

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Hugh Scott, Sublette, Kansas
Producing formation none Depth to top Bottom Total Depth of Well 5600 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface Sands	water	400'	600'			
Cimarron Anhy	saltwater	1700'	1940'	8 5/8	1951'	
Hugoton pays	gas	2485	2698			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

1st plug 2600' 70 sx
2nd plug 700' 35sx
3rd plug 40' Filled to surface

RECEIVED
STATE CORPORATION COMMISSION

JUN 24 1963 06-24-63

CONSERVATION DIVISION
Wichita, Kansas

Name of Plugging Contractor Wakefield Drilling Company
Address Wichita, Kansas
(If additional description is necessary, use BACK of this sheet)

STATE OF Kansas, COUNTY OF Seward, ss.
R. Woody Paul (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. Woody Paul
Liberal, Kansas

(Address)

SUBSCRIBED AND SWORN TO before me this 18 day of June 19 63

My commission expires Feb. 28, 1967

Phyllis J. Rodzyrna
Notary Public.

DRILLERS LOG

LEASE: H. E. JOHNSTON No. 1
 OPERATOR: E. E. FOGELSON
 CONTRACTOR: EARL F. WAKEFIELD
 COMMENCED DRILLING: 5-16-63
 COMPLETED 6-6-63

LOCATION: C NE SW
 SECTION 17-26S-38W
 KEARNEY COUNTY, KANSAS
 CASING: 8 5/8" Set at 1948'

	From	To
Surface Clay	0	41
Sand and Surface Clay	41	610
Red Bed with Shale	610	800
Anhydrite	800	815
Red Bed With Anhydrite	815	960
Shale, Anhydrite, Sand	960	1230
Anhydrite & Red Bed	1230	1415
Anhydrite With Shale	1415	1665
Shale and Anhydrite	1665	1951
Red Shale & Anhydrite Stks.	1951	2315
Red Bed & Shale	2315	2514
Shale and Lime	2514	2698
Lime and Shale	2698	2850
Lime & Shale W/streaks chalk	2850	3045
Lime and Shale	3045	3525
Lime	3525	3741
Lime W/Shale Streaks	3741	3808
Lime	3808	4146
Lime & Chert	4146	4255
Lime and Shale	4255	4323
Lime	4323	4690
Lime and Shale	4690	4860
Lime	4860	4945
Lime and Shale	4945	4994
Lime	4994	5045
Lime and Shale	5045	5195
Lime W/Shale	5195	5248
Lime and Shale	5248	5362
Lime	5362	5600
T.D.	5600	

RECEIVED
 STATE CORPORATION COMMISSION

JUN 24 1963

CONSERVATION DIVISION
 Wichita, Kansas

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

I hereby certify that the above is a true and correct copy of the log on the H. E. JOHNSTON Well No. 1, located C NE SW of Section 17, Township 26 South, Range 38 West, Kearney County, Kansas.

EARL F. WAKEFIELD

By Fred S. Barker

Subscribed and sworn before me this 14th day of June, 1963.

My commission expires:
January 25, 1965

Wanda W. Riley
 WANDA W. RILEY NOTARY