

STATE OF KANSAS  
 STATE CORPORATION COMMISSION  
 200 Colorado Derby Building  
 Wichita, Kansas 67202

WELL PLUGGING RECORD  
 K.A.R.-82-3-117

API NUMBER 15-203-20,083-06-00

LEASE NAME MC MICHAEL

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

WELL NUMBER 1

4620 Ft. from S Section Line

1980 Ft. from E Section Line

SEC. 33 TWP. 20S RGE. 35W (E) or (W)

COUNTY Kearny

Date Well Completed 7/21/85

Plugging Commenced 7/21/85

Plugging Completed 7/21/85

LEASE OPERATOR Great Plains Resources

ADDRESS P.O. Box 369, Littleton, CO 80160

PHONE# (303) 979-4029 OPERATORS LICENSE NO. 5449

Character of Well DRY

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? YES

Which KCC/KDHE Joint Office did you notify? Clyde Wiley

Is ACO-1 filed? NO If not, is well log attached? no

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 5050'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

1st plug @ 2290' w/50 sx. 15 sx. in Rathole. Plug down 11:45 a.m.,

2nd plug @ 455' w/50 sx. 10 sx. in Mousehole. 7/21/85

3rd plug @ 40' Sol. Bridge w/10 sx. 60-40 pozmix, 6% gel.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Abercrombie Drilling, Inc. License No. 5422

Address 801 Union Center, Wichita, KS 67202

STATE OF Kansas COUNTY OF Sedgwick, ss.


Jack L. Partridge, Vice President (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Jack L. Partridge  
Jack L. Partridge, Vice President  
 (Address) 801 Union Cntr., Wichita, KS 67202

SUBSCRIBED AND SWORN TO before me this 23rd day of July, 1985

Elizabeth G. Brittain  
 Notary Public  
 Elizabeth G. Brittain

My Commission Expires: 7-13-85



**ORIGINAL INVOICE**



A DIVISION OF HALLIBURTON COMPANY

REMIT TO:  
P.O. BOX 84737  
DALLAS, TX 75284

INVOICE NO.	DATE
089931	07/21/1985

WELL LEASE NO.	WELL LOCATION	STATE	WELL OWNER		
CMICHAEL 3	WICHITA	KS	SAME		
SERVICE LOCATION	CONTRACTOR	JOB PURPOSE	TICKET DATE		
IBERAL	ABERCROMBIE	PLUG TO ABANDON	07/21/1985		
ACCT. NO.	CUSTOMER AGENT	VENDOR NO.	CUSTOMER P.O. NUMBER	SHIPPED VIA	
40819	J. W. TOWNS			HALLIBURTON	04755

GREAT PLAINS RESOURCES  
BOX 369  
LITTLETON, CO 80160

DIRECT CORRESPONDENCE TO:  
SUITE 600  
COLORADO DERBY BUILDING  
WICHITA, KS 67202-0000

PRICE REF. NO.	DESCRIPTION	QUANTITY	U/M	UNIT PRICE	AMOUNT
000-117	MILEAGE	58	MI	2.10	121.80
009-019	PLUG-BACK / SPOT CEMENT OR MUD	1	PMP	879.00	879.00
		2890	FT		
030-015	DMTG PLUG(5 WIPER)	1	EA	129.00	129.00
		10	3/4 IN		
304-043	STANDARD CEMENT	81	SK	6.62	536.22
306-105	POZMIX A	54	SK	3.60	194.40
306-121	HALLIBURTON-GEL 2%	2	SK	.00	N/C
307-277	HALLIBURTON-GEL BENTONITE	135	SK	.37	49.95
300-207	BULK SERVICE CHARGE	135	CFT	.95	128.25
300-306	MILEAGE	510.699	TMI	.70	357.49
INVOICE SUBTOTAL					2,396.11
*-KANSAS STATE SALES TAX					71.88
*-SEWARD COUNTY SALES TAX					23.95
DATE REC'D <u>072585</u> DUE DATE <u>082585</u>					
INVOICE # <u>89931</u>					
VENDOR # <u>1086</u> G/L PSTG. ACCT. # <u>591</u>					
WELL # / OH <u>181</u> COST CODE # <u>228</u>					
AMOUNT OF INVOICE <u>2491.94</u>					
(DISCOUNT)/CHARGE AMOUNT <u>✓</u>					
AMOUNT TO PAY <u>✓</u>					
PAYMENT APPROVAL <u>✓</u>					
DATE PAID <u>8/25/85</u> CHECK # <u>8477</u>					
INVOICE TOTAL - PLEASE PAY THIS AMOUNT =====>					\$2,491.94

**JUL 25 RECD**

TERMS INVOICES PAYABLE NET BY THE 20TH OF THE FOLLOWING MONTH AFTER DATE OF INVOICE. UPON CUSTOMER'S DEFAULT IN PAYMENT OF CUSTOMER'S ACCOUNT BY THE LAST DAY OF THE MONTH FOLLOWING THE MONTH IN WHICH THE INVOICE IS DATED, CUSTOMER AGREES TO PAY INTEREST THEREON AFTER DEFAULT AT THE HIGHEST LAWFUL CONTRACT RATE APPLICABLE BUT NEVER TO EXCEED 18% PER ANNUM. IN THE EVENT IT BECOMES NECESSARY TO EMPLOY AN ATTORNEY TO ENFORCE COLLECTION OF SAID ACCOUNT, CUSTOMER AGREES TO PAY ALL COLLECTION COSTS AND

ABERCROMBIE DRILLING, INC.

801 UNION CENTER  
WICHITA, KANSAS 67202

MC MICHAEL #3 (Rig #5)

NW NE

Sec. 33-20S-35W

Kearny Co., KS

Great Plains Resources

P.O. Box 369

Littleton, CO 80160

303-979-4029

L.L. Tuck

OPERATOR: Great Plains Resources

CONTRACTOR: Abercrombie Drilling, Inc.

ELEVATION: G.L. 3180'

D.F. 3183'

K.B. 3185'

- 7/18/85 Drilling @ 4625'. Cut 95'/24 hrs. 7½ hrs. Drlg., 16½ hrs. DW. Bit #3, HP-53A (SN NO 1335) Mud wt. 9.2, Visc. 60, PV/YP 16/24, gels 14/22, WL 8.4, ph 10.5, 27,000 Chl., 5.6% Sol., LCM-1#. Daily mud \$1010.00, Acc. mud \$5448.00. Bit wt. 38,000# @ 60 RPM. Pump press. 1000# @ 48 SPM.
- 7/19/85 Drilling @ 4785'. Cut 160'/24 hrs. 12½ hrs. Drlg., 11½ hrs. DW, ½ hrs. Other. Bit #3, HP-53A, (SN NO 1335) Mud wt. 9.2, Visc. 49, PV/YP 18/28, gels 15/27, WL 9.4, ph 10.5, 29,000 Chl., 5.3% Sol. Daily mud \$532.00. Acc. mud \$5980.00. Bit wt. 40,000# @ 65 RPM. Pump press. 1000# @ 50 SPM.
- 7/20/85 Drlg. @ 4970'. Cut 185'/24 hrs. 12½ hrs. Drlg., 11½ hrs. DW, ¼ hrs. Rep., ¼ hrs. Other. Bit #3, HP-53A, (SN MO 1335) Mud wt. 9.1, Visc. 51, PV/YP 16/24, gels 10/28, WL 9.9, ph 10.5, 21,000 Chl., 5.1% Sol., Daily mud \$375.00, Acc. mud \$6355.00. Bit wt. 38,000# @ 55 RPM. Pump press. 1000# @ 48 SPM.
- 7/21/85 5050' TD. Preparing to plug. Cut 80'/24 hrs. 5½ hrs. Drlg., 18½ hrs. DW, ¼ hrs. Other. Bit #3, HP-53, in @ 4333', out @ 5050', cut 717'/48 ¾ hrs. Daily mud \$306.00, Acc. mud \$6661.00.
- 7/22/85 5050' TD. 1st plug @ 2290'/50 sx. 2nd plug @ 455'/50 sx. 3rd plug @ 40' Sol. Bridge w/10 sx. 15 sx. in Rathole. 10 sx. in Mousehole. 60-40 poz., 6% gel. Cement by Halliburton. State plugger Clyde Wiley. Plug down 11:45 a.m., 7/21/85.

DEVIATIONS:

5050' - 3/4°

JUL 23 1985