

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-155-02323-0000

LEASE NAME Peace Creek Unit

WELL NUMBER #1601W

2310' FNL & 1650' FWL
SPOT LOCATION _____

SEC. 6 TWP. 23 RGE. 9W (E) or (W)

COUNTY Reno

Date Well Completed _____

Plugging Commenced 4-30-86

Plugging Completed 5-7-86

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Kelso Casing Pulling Bought From/Cities Service
Oil & Gas Corporation.

ADDRESS Box 347 Chase, Ks 67524

PHONE [(316) 938-2457] OPERATORS LICENSE NO. 5447

Character of Well Inj.
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Wichita, Kansas

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing formation _____ Depth to top _____ bottom _____ T.D. 3754'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	205'	none
				5-1/2"	3720'	1522'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.
Plugged off bottom with sand to 3700' and 5 sacks cement. Shot pipe @2739', 2533', 2321', 2125', 1938', 1740', 1524', pulled a total of 59 joints (1522') of 5-1/2" casing.
Plugged surface with 3 hulls, 15 gel, 115 cement, 60/40 pos, 3% gel, 3% cc.
Plugging Complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling License No. 6050
Address Box 347 Chase, Kansas 67524


STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R. Darrell Kelso
(Address) Box 347 Chase, Ks. 67524

SUBSCRIBED AND SWORN TO before me this 12th day of May, 1986

My Commission expires: _____



Irene Hoover
Notary Public