

STATE OF KANSAS  
 STATE CORPORATION COMMISSION  
 200 Colorado Derby Building  
 Wichita, Kansas 67202

WELL PLUGGING RECORD  
 K.A.R.-82-3-117

20830 00  
 API NUMBER 15-063-830-00

LEASE NAME Turner

WELL NUMBER #1

SPOT LOCATION NE NE NE

SEC. 34 TWP. 13 RGE. 30 (W) of (W)

COUNTY Gove

Date Well Completed \_\_\_\_\_

Plugging Commenced 4-11-85

Plugging Completed 4-18-85

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

LEASE OPERATOR White and Ellis Drilling, Inc.

ADDRESS 401 E. Douglas, Suite 500, Wichita, Ks. 67202

PHONE # (316-263-1102) OPERATORS LICENSE NO. 5420

Character of Well oil  
 (Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Six

Is ACO-1 filed? \_\_\_\_\_ If not, is well log attached? With application

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom T.D. 4480'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	379'	None
				4-1/2"	4480'	2,521.12'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

Dumped 4 sacks cement on bottom, sanded back to 4150' and dumped 4 sacks cement. Shot casing at 3800', 3000', 2750' and 2500'. Pulled 60 joints of 4-1/2" casing. Squeezed well with 4 sacks hulls, 29 sacks gel, 100 sacks cement, 1 sack gel, 50 sacks cement, 8 sacks gel, released plug and pumped 10 sacks 50/50 pozmix cement with 6% added gel and 3% calcuim chloride. Maximum pressur was 700 psi-shutin 300 psi. Filled rathole with 20 sacks cement.

Name of Plugging Contractor Rockhold Engineering, Inc. License No. 5111  
 Address Box 698, Great Bend, Ks. 67530

STATE OF Kansas COUNTY OF Barton, ss.

James W. Rockhold (employee of operator) or  
 (operator) of above-described well, being first duly sworn on oath, says: That  
 I have knowledge of the facts, statements, and matters herein contained and  
 the log of the above-described well and that the same are true and  
 correct, so help me God.

APR 23 1985  
 4-23-85

(Signature) James W. Rockhold  
 (Address) Box 698, Gt. Bend, Ks. 67530

CONSERVATION DIVISION  
 Wichita, Kansas  
 SUBSCRIBED AND SWORN TO before me this 22nd day of April, 1985  
 IONA M. LEATHERMAN  
 Barton County, Kansas  
 My Appt. Exp. 9-26-87

Iona M. Leatherman  
 Notary Public

My Commission expires: \_\_\_\_\_