


WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

Gove County, Sec. 20 Twp. 11 Rge. 31 (E) W (W)

NORTH



Locate well correctly on above Section Plat

Location as "NE/CNW/SW" or footage from lines C NE NE  
Lease Owner Terrel Drilling & Producing  
Lease Name Wieland Well No. 1  
Office Address Russell, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) \_\_\_\_\_  
Date well completed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging filed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging approved \_\_\_\_\_ 19\_\_\_\_  
Plugging commenced 1-23-64 19\_\_\_\_  
Plugging completed 1-25-64 19\_\_\_\_  
Reason for abandonment of well or producing formation Depleted.

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well W. L. Nichols  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4652 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	250'	None
				4-1/2"	4651'	1508'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Checked hole to plug back @ 4445', sanded hole to 4415' and dumped 2 sacks of cement @ 4415' with dump bailer. Pulled 4 1/2" casing to 600' and circulated pipe with 16 sacks of gel mud and 20 sacks of cement. Pulled 4 1/2" casing to 250' and pumped in 20 more sacks of cement @ 250'. Pulled balance of 4 1/2" casing, bailed fluid to 30' and ran 10 sacks of cement to base of cellar.

PLUGGING COMPLETE.

RECEIVED  
STATE CORPORATION COMMISSION  
FEB 17 1964  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor KNIGHT CASING PULLING COMPANY  
Address CHASE, KANSAS

STATE OF KANSAS, COUNTY OF RICE, ss.  
Noel J. Knight (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel J. Knight  
Chase, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 31st day of January, 1964

My commission expires May 20, 1964

Milton J. Tolis  
Notary Public.

AK

15.063.00-106.00.00

RECEIVED  
STATE CORPORATION COMMISSION

JAN 8 1964

CONSERVATION DIVISION  
Wichita, Kansas

W E L L L O G

OPERATOR: Fred B. Anschutz  
1521 Wichita Plaza  
Wichita, Kansas

CONTRACTOR: Terrel Drilling & Producing  
Box 606  
Russell, Kansas

LEASE: Weiland #1

COMMENCED: December 14, 1963

LOCATION: C NE NE Sec. 20-11S-31W  
Gove County, Kansas

COMPLETED: January 5, 1964

DEPTHS & FORMATIONS


Hard Sand	150	Lime & Shale	3385
Shale & Shells	255	Lime w/ Shale	3430
Clay & Shale	906	Shale & Lime	3498
Shale & Shells	2012	Lime & Shale	3635
Shale & Lime	2168	Lime w/ Shale	3885
Shale	2485	Lime & Shale	3950
Anhydrite	2525	Lime	4530
Shale	2535	Bentnite	4535
Shale & Shells	2790	Lime & Shale	4596
Lime w/ Shale	3045	Lime (R.T.D.)	4650

STATE OF KANSAS )  
                          )  
COUNTY OF RUSSELL) ss..

Joe K. Branum, owner of Terrel Drilling and Producing, being first duly sworn on oath says: "That I have knowledge of the facts, statements and matters herein contained and the log of the above described well as filed and that the same are true and correct."

  
Joe K. Branum-TERREL DRILLING AND PRODUCING

Subscribed and sworn before me this 7th day of January, 1964

  
Notary Public

My Commission Expires December 12, 1966.