

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Gove County, Sec. 6 Twp. 14 Rge. 27 (E) W (W)

Location as "NE/CNW/SE" or footage from lines C NE SE

Lease Owner Tidewater Oil Company

Lease Name B. A. Hutton Well No. 1

Office Address 1101 Hales Building, Oklahoma City, Oklahoma

Character of Well (completed as Oil, Gas or Dry Hole)

Date well completed 19

Application for plugging filed 19

Application for plugging approved 19


Plugging commenced 4-1-64 19

Plugging completed 4-7-64 19

Reason for abandonment of well or producing formation Depleted.

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well W. L. Nichols

Producing formation Depth to top Bottom Total Depth of Well 4117 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUL IN	PULLED OUT
					360'	None
				5-1/2"		3132'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Checked hole to 4117', pushed plug to 3860', sanded to 3700' and dumped 5 sacks of cement @ 3700' with dump bailer. Pulled casing to 600' and circulated with 26 sacks of gel mud. Pulled 5 1/2" casing to 540' and dumped 20 sacks of cement @ 540'. Pulled 5 1/2" casing to 360' and dumped 20 sacks of cement @ 360'. Mudded hole to 30' and ran 10 sacks of cement to base of cellar.

RECEIVED
STATE CORPORATION COMMISSION

APR 16 1964

PLUGGING COMPLETE.

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor KNIGHT CASING PULLING COMPANY

Address CHASE, KANSAS

STATE OF KANSAS, COUNTY OF RICE, ss.

Noel J. Knight (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel J. Knight

Chase, Kansas

(Address)

SUBSCRIBED AND SWORN TO before me this 9th day of April, 1964

Milton J. Volin
Notary Public.

My commission expires May 20, 1964

15.063.00.105.00.00

DRILLERS LOG

B. A. Hutton No. 1

CASING RECORD:	COMPANY:	Tidewater Oil Co.	DESCRIPTION:
8 5/8" @ 373.42'	CONTRACTOR:	Red Tiger Drilling Co.	C NE SE
w/300 sx cement	COMMENCED:	February 10, 1964	6-14S-27W
5 1/2" @ 4420'	COMPLETED:	February 24, 1964	Gove County, Kansas
w/250 sx cement			ELEVATION: 2566 DF
			2569 RB
TOTAL DEPTH: 4420'			

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Sand & Shale	0	60	<p style="text-align: center;">RECEIVED STATE CORPORATION COMMISSION</p> <p style="text-align: center;">APR 1 1964</p> <p style="text-align: center;">CONSERVATION DIVISION Wichita, Kansas</p>
Shale	60	965	
Sand & Shale	965	1045	
Shale	1045	1561	
Blain Anhydrite	1561	1570	
Shale	1570	2023	
Anhydrite	2023	2064	
Shale	2064	2440	
Shale & Lime	2440	2895	
Lime	2895	3365	
Lime & Shale	3365	3470	
Lime	3470	4420	

I certify that this is a true and correct copy of the above log to the best of my knowledge.

RED TIGER DRILLING COMPANY

Maxine V. Head
Maxine V. Head

Subscribed and sworn to before me this 26th day of February, 1964.

Jean Hollan
Notary Public

My Commission Expires:

5-22-66