


15.063.30082.00.00

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Gove County, Sec. 27 Twp. 14 Rge. (E) 26(W)

NORTH



Locate well correctly on above
Section Plat

Location as "NE/CNW%SW%" or footage from lines SE SE NW
Lease Owner Pickrell Drilling Company
Lease Name Albin "A" Well No. 1
Office Address 705 4th National Bank Building, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed February 14, 1966
Application for plugging filed February 14, 1966
Application for plugging approved February 14, 1966
Plugging commenced February 14, 1966
Plugging completed February 14, 1966
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well W. L. Nichols
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4330 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	223'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Heavy mud to 210', set plug. Cemented with
20 sacks cement. Heavy mud to 40', set plug.
Cemented with 10 sacks cement to bottom of
cellar. Plugged rat hole with 2 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION

FEB 23 1966

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Pickrell Drilling Company
Address 705 4th National Bank Bldg, Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

C. W. SEBITS (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C. W. Sebits
705 4th National Bank Bldg, Wichita, Kansas
(Address)

Subscribed AND SWORN to before me this 17th day of February, 1966



My commission expires June 21, 1966

Maxine Blackman
Notary Public.

ROTARY DRILLING LOG

COMPANY: PICKRELL DRILLING COMPANY Rotary Drilling Commenced 2-4-66
 705 4th Natl Bank Bldg.
 Wichita, Kansas Rotary Drilling Completed 2-14-66
 LOCATION: Albin "A" No. 1, SE SE NW Section 27-14-26W, Gove County, Kansas

CONTRACTOR: **PICKRELL DRILLING COMPANY**
 Wichita, Kansas

CASING RECORD: (10 jts) 8 5/8" surface casing set at 223' cemented with 145 sacks cement. Circulated. Completed 6:00 P.M. February 4, 1966. No oil string run, D & A.

LOG

(Figures indicate bottom of formation — measurements from top of rotary bushing.)

40	Post Rock	C. F. S.
224	Shale & Shells	3817
710	Shale, some sand	3868
1005	Shale & Shells	3892
1285	Red Bed, Shale & Shells	3938
1315	Blaine	3955
1385	Shale & Shells	4207
1630	Sand	4227
1864	Shale	4285
1902	Anhydrite	4292
2075	Shale	4320
2310	Shale & Shells	4330
2675	Lime & Shale	
2805	Lime	Slope Tests
2980	Lime & Shale	2500
3210	Lime	3000
3362	Lime & Shale	3500
3500	Shale	4000
3655	Lime	
3745	Lime & Shale	S. L. M.
3868	Lime	3574
3920	Lime & Shale	3904
3955	Lime	4263
4040	Lime & Shale	
4155	Lime	
4294	Lime & Shale	
4330	Mississippian - RTD	

RECEIVED
 STATE CORPORATION COMMISSION

FEB 23 1966

CONSERVATION DIVISION
 Wichita, Kansas

The undersigned, C. W. SEBITS, Attorney-in-Fact for PICKRELL DRILLING COMPANY, hereby certifies in behalf of said Company, that the above is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

PICKRELL DRILLING COMPANY

By: *C. W. Sebits*
 C. W. SEBITS, Attorney-in-Fact

STATE OF KANSAS }
 COUNTY OF SEDGWICK } ss.:

On this 17th day of February, 19 66, before me the undersigned, a Notary Public, in and for the County and State aforesaid, personally appeared C. W. SEBITS, to me known to be the identical person who subscribed the name of PICKRELL DRILLING COMPANY to the foregoing instrument as its Attorney-in-Fact and acknowledged to me that he executed the same as his free and voluntary act and deed, and as the free and voluntary act and deed of such company, for the uses and purposes therein set forth.

Given under my hand and seal of office the day and year last above written.

My commission expires: June 21, 1966

Maxine Blackman
 Maxine Blackman, Notary Public