


15.063.30040.00.00
WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Gove County, Sec. 25 Twp. 14 Rge. 26 (E) W (W)

NORTH



Locate well correctly on above
Section Plat

Location as "NE/CNW/SW" or footage from lines NE/NE
Lease Owner Leo J. Dreiling Oil Company
Lease Name Humburg Well No. 1
Office Address Route # 2 Victoria, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry
Date well completed 4-28-1965
Application for plugging filed 4-28-1965
Application for plugging approved 4-28-1965
Plugging commenced 4-28-1965
Plugging completed 4-28-1965
Reason for abandonment of well or producing formation -0- ~~4-28-~~

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well W.L. Nichols
Producing formation -0- Depth to top -0- Bottom -0- Total Depth of Well 445' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
SURFACE PIPE				8-5/8"	222'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole to a depth of 540' with rotary mud and 1st plug was set using 20 sacks cement. Filled hole with rotary mud to a depth of 210' where 2nd plug was set using 20 sacks cement. Rotary mud was used to fill hole to a depth of 40' where 3rd plug was set using 10 sacks cement and filling hole to surface.

RECEIVED
STATE CORPORATION COMMISSION

MAY 6 1965 5-6-65

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor L.J. DREILING & SONS, INC.
Address VICTORIA, KANSAS

STATE OF Kansas, COUNTY OF Ellis, ss.
I, Leo F. Dreiling, a partner (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Leo F. Dreiling
LEO F. DREILING VICTORIA, KANSAS
(Address)

SUBSCRIBED AND SWORN TO before me this 29 day of April, 19 65

Elmer Weltz
Elmer Weltz Notary Public.

My commission expires October 26, 1968

L. J. DREILING and SONS, Inc.

VICTORIA, KANSAS

15 063 300 10.00.00

WELL LOG

Company LEO J. DREILING OIL CO.
VICTORIA, KANSAS

Sec. 25 Twp. 14 Rng. 26

Farm Humburg No. # 1

Location NE/NE

Total Depth 4415'

County Gove

Comm. 4-19-65

Comp. 4-28-65

Elevation: 2378' D. F.

Contractor L.J. Dreiling & Sons, Inc.
Victoria, Kansas

2383' G. R.

Casing Record

Cement Record

Production:

222' 8-5/8"

150 sacks

D & A

Figures Indicate Bottom of Formations

0'	40'	Surface Soil & Post Rock
40'	90'	Clay & Shale
90'	222'	Shale
222'	646'	Shale
646'	867'	Shale & Red Bed
867'	976'	Shale & Red Bed
976'	980'	Pydrite
980'	1284'	Red Bed & Shale
1284'	1297'	Anhy.
1297'	1405'	Shale
1405'	1635'	Sand & Shale
1635'	1861'	Red Bed & Shale
1861'	1900'	Anhy.
1900'	1965'	Shale & Shells
1965'	2313'	Shale & Shells
2313'	2515'	Shale & Lime
2515'	2700'	Lime
2700'	2863'	Lime & Shale
2863'	2990'	Lime
2990'	3103'	Lime
3103'	3214'	Lime & Shale
3214'	3454'	Lime & Shale
3454'	3585'	Lime & Shale
3585'	3665'	Lime & Shale
3665'	3766'	Lime
3766'	3823'	Lime
3823'	3919'	Lime
3919'	3976'	Lime
3976'	4068'	Lime
4068'	4135'	Lime
4135'	4198'	Lime
4198'	4263'	Lime
4263'	4311'	Lime
4311'	4348'	Lime
4348'	4415'	Miss.
4415'	T.D.	

RECEIVED
STATE CORPORATION COMMISSION

MAY 6 1965

CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS)

ELLIS COUNTY)

ss

I, Leo F. Dreiling, of the L.J. Dreiling & Sons, Inc. upon oath states that the above and foregoing is a true and correct copy from the Daily Drilling Report from your Humburg # 1.

Leo F. Dreiling
LEO F. DREILING

Subscribed and sworn to before me this 29th day of April, 1965.

My commission expires: October 26, 1968

Elmer J. Kelly
NOTARY PUBLIC