


15.063.20229.00.00

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
P. O. Box 17027  
Wichita, Kansas 67217  
NORTH

WELL PLUGGING RECORD



Locate well correctly on above Section Plat

Gove County. Sec. 18 Twp. 14 Rge. 26W (E) (W)  
Location as "NE/CNW/SW" or footage from lines. C SE NW  
Lease Owner Chief Drilling Co., Inc. & Bill J. Porter  
Lease Name Herl Well No. 1  
Office Address Suite 905 Century Plaza, Wichita, Kansas 67202  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed 9/1/74 19  
Application for plugging filed 8/31/74 19  
Application for plugging approved 8/31/74 19  
Plugging commenced 9/1/74 19  
Plugging completed 9/1/74 19  
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Bill Nichols  
Producing formation Depth to top Bottom Total Depth of Well 4375 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	287'	8 5/8"		

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plugged through drill pipe @ 1400' w/75 sacks common quick set 6% gel.

RECEIVED  
STATE CORPORATION COMMISSION  
SEP 6 1974  
CONSERVATION DIVISION  
Wichita, Kansas

9-6-74


(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Chief Drilling Co., Inc.  
Address Suite 905 Century Plaza, Wichita, Kansas 67202

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.  
Jim Robinson (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Jim Robinson  
Suite 905 Century Plaza, Wichita, Kansas 67202  
(Address)

SUBSCRIBED AND SWORN to before me this 3rd day of September, 1974

My commission expires August 5, 1975  
Virginia S. Fabian, Notary Public.



WELL LOG

CHIEF DRILLING CO., INC. & BILL J. PORTER  
Suite 905 Century Plaza  
Wichita, Kansas 67202

#1 HERL  
C SE NW Sec. 18-14-26W  
Gove County, Kansas

CONTRACTOR: Chief Drilling Co., Inc.  
CASING RECORD: Set 281' of 8 5/8" w/165 sacks  
common quick set cement

COMMENCED: 8/21/74  
COMPLETED: 9/1/74

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>ELEVATION</u>
Surface Clay & Sand	0	290	2496 Gr.
Sand & Shale	290	497	2498 D.F.
Shale & Sand	497	1951	2501 K.B.
Shale	1951	2195	
Shale & Shells	2195	3109	
Shale	3109	3402	
Shale & Shells	3402	3438	
Shale	3438	3638	
Shale & Lime	3638	3835	
Lime & Shale	3835	4025	
Lime	4025	4030	
Lime & Shale	4030	4190	
Lime	4190	4375	
Total Depth	4375		

ELECTRIC LOG TOPS

Anhydrite	1945 +	556
Base Anhy.	1982 +	519
Heebner	3694 -	1193
Toronto	3719 -	1218
Lansing	3731 -	1230
B.K.C.	4030 -	1529
Ft. Scott	4224 -	1723
Conglomerate	4295 -	1794
Reworked Miss.	4313 -	1812
Miss. Dolomite	4322 -	1821
L.T.D.	4375 -	1874

RECEIVED  
STATE CORPORATION COMMISSION  
SEP 6 1974  
CONSERVATION DIVISION  
Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK) ss:

I hereby certify that the above is a true and correct copy of the Driller's Log of the well deilled in the C SE NW of Section 18-14-26W, Gove County, Kansas, to the best of my knowledge and belief.

CHIEF DRILLING CO., INC.

Jim Robinson  
Jim Robinson, Vice President

Subscribed and sworn to before me this 5th day of September, 1974.

Virginia S. Fabian  
Virginia S. Fabian, Notary Public

