


WELL PLUGGING RECORD

15-09501006-000

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Kingman County. Sec. 19, Twp. 29S, Rge. (E) 6 (W)
Location as "NE/CNW%SW%" or footage from lines 150' S of C NW SW
Lease Owner Pickrell Drilling Company
Lease Name COX "B" Well No. 3
Office Address 705 4th National Bank Bldg, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed February 20, 1966
Application for plugging filed February 20, 1966
Application for plugging approved February 20, 1966
Plugging commenced February 20, 1966
Plugging completed February 20, 1966
Reason for abandonment of well or producing formation Dry Hole

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Archie V. Elving
Producing formation Depth to top Bottom Total Depth of Well 3790 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 4/8"	207'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Heavy mud to 200', set plug, cemented with

25 sacks cement. Heavy mud to 40', set plug.

Cemented with 10 sacks cement to bottom of cellar.

Plugged rat hole with 2 sacks Cement.

RECEIVED
STATE CORPORATION COMMISSION

03-01-66 MAR 1 1966

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Pickrell Drilling Company
Address 705 4th Natl Bank Bldg, Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

C. W. SEBITS (owner or operator) of the above-described well, being first duly sworn, on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

C. W. Sebits,
705 4th National Bank Building, Wichita, Ks.
(Address)

Subscribed and sworn to before me this 24th day of February, 1966

Maxine Blackman
Maxine Blackman, Notary Public.

My commission expires June 21, 1966

ROTARY DRILLING LOG

15-095-01006-0000

COMPANY: PICKRELL DRILLING COMPANY
705 4th Nat'l Bank Bldg.
Wichita, Kansas

Rotary Drilling Commenced 2-12-66

Rotary Drilling Completed 2-20-66

LOCATION: Cox "B" No. 3, 150' South of Center NW SW Section 19-29S-6W, Kingman County, Ks.

CONTRACTOR: **PICKRELL DRILLING COMPANY**
Wichita, Kansas

CASING RECORD: (10 jts) 8 5/8" surface casing set at 207' cemented with 150 sacks cement. Circulated. Completed 7:45 P.M. February 12, 1966. No oil string run, D & A.

LOG

(Figures indicate bottom of formation — measurements from top of rotary bushing.)

60	Sand	<u>C. F. S.</u>
208	Red Rock	3305
608	Red Bed & Shale	3325
1240	Shale, Shells & Lime	3706
3000	Lime & Shale	3736
3305	Sand, Shale & Lime	3775
3400	Lime & Shale	3790
3580	Lime	
3672	Shale & Lime	<u>Slope Tests</u>
3718	Lime	2500
3736	Lime & Shale	3000
3790	Lime & RTD	3300
		3650
		<u>S. L. M.</u>
		2997
		3302
		3665

RECEIVED
STATE CORPORATION COMMISSION
MAR 1 1966
CONSERVATION DIVISION
Wichita, Kansas

The undersigned, C. W. SEBITS, Attorney-in-Fact for PICKRELL DRILLING COMPANY, hereby certifies in behalf of said Company, that the above is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

PICKRELL DRILLING COMPANY
By [Signature]
C. W. SEBITS, Attorney-in-Fact

STATE OF KANSAS }
COUNTY OF SEDGWICK } ss.:

On this 24th day of February, 1966, before me the undersigned, a Notary Public, in and for the County and State aforesaid, personally appeared C. W. SEBITS, to me known to be the identical person who subscribed the name of PICKRELL DRILLING COMPANY to the foregoing instrument as its Attorney-in-Fact and acknowledged to me that he executed the same as his free and voluntary act and deed, and as the free and voluntary act and deed of such company, for the uses and purposes therein set forth.

Given under my hand and seal of office the day and year last above written.

My commission expires: June 21, 1966
Maxine Blackman
Maxine Blackman, Notary Public