

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-095-21139 ~~0000~~

LEASE NAME Osborn

WELL NUMBER 1

 Ft. from S Section Line

 Ft. from E Section Line

SEC. 19 TWP. 29 SRGE. 6 ~~XXXX~~ (W)

COUNTY Kingman

Date Well Completed

Plugging Commenced Oct. 30, 1989

Plugging Completed Oct. 31, 1989

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Robert E. Campbell

ADDRESS 260 N. Rock Road #110 Wichita, Ks. 67206

PHONE# (316) 685-6001 OPERATORS LICENSE NO. 5348

Character of Well Gas

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on Oct. 31, 1989 (date)

by Doug Lewis (KCC District Agent's Name).

Is ACO-1 filed? yes If not, Is well log attached?

Producing Formation Depth to Top Bottom T.D. 4153

Plug back TD 4149

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
		0	240	8 5/8	240'	none
				3/4" rods	164	164
				2 3/8" tubing	127	127
			4152	4 1/2"	4152	1500'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Oct. 30: Rigged up and pulled and layed down the rods, tubing Sanded back to 4120",
 dumped 5 sx. cement on top of sand.

Oct. 31: Cut off and pulled 1500' of 4 1/2" casing.

Oct. 31: spotted 50' plug at 1100', spotted 50' plug at 600', 35 sx. at 300', spot 25 sx. at 60' (if additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Pratt Well Service, Inc. License No. 5893

RECEIVED
 STATE CORPORATION COMMISSION

Address P.O. Box 847 Pratt, Ks. 67124

NOV 15 1989

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Robert E. Campbell


STATE OF Kansas COUNTY OF Pratt, ss.

CONSERVATION DIVISION
 Wichita, Kansas

Judy Berry (Employee/~~XXXXXXXXXXXXXXXXXXXX~~ of plugging contractor.
 above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Judy Berry

(Address) Box 847 Pratt, Ks.



SUBSCRIBED AND SWORN TO before me this 14th day of November, 19 89

Dorothy M. Ferguson
 Notary Public

My Commission Expires: February 6, 1993

