

15095-20747-000

RECEIVED  
STATE CORPORATION COMMISSION

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD


AUG 31 1978  
08-31-78

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.  
245 North Water  
Wichita, KS 67202

Kingman County, Kansas  
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines  
100' N of C-SW SW

Lease Owner Zorger Oil Company  
Lease Name McCormick Well No. 1  
Office Address 1010 Douglas Bldg., 104 S. Broadway,  
Character of Well (Completed as Oil, Gas or Dry Hole) Dry Hole  
Wichita KS 67202

Date Well completed August 23, 1978  
Application for plugging filed Verbal Application 1978  
Application for plugging approved Verbal Approval 1978  
Plugging commenced August 23, 1978  
Plugging completed August 23, 1978  
Reason for abandonment of well or producing formation \_\_\_\_\_



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production 19\_\_\_\_

Was permission obtained from the Conservation Division or  
its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Carl Barnett  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4,154'  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	237'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled hole with heavy rotary mud from 4,154 ft. (rotary total depth) to 230 ft. Set plug at 230 ft. and cemented with 20 sacks cement. Filled hole with heavy rotary mud from 230 ft. to 40 ft. Set solid plug at 40 ft. and cemented to cellar with 10 sacks cement, 2 sacks cement in Rat hole.

Plugging operations accomplished utilizing Allied Oil Well cementing pump truck through 4 1/2 inch drill pipe.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Allied Cementing Co., Inc.  
Box 31, Russell, Kansas 67665

STATE OF Kansas COUNTY OF Sedgwick, ss.  
Dean Britting, Agent ~~XXXXXXXXXXXXXXXXXXXX~~ of owner ~~XXXXXXXXXXXXXXXXXXXX~~

of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Dean Britting  
200 N. Main, Wichita, Kansas 67202  
(Address)

SUBSCRIBED AND SWORN TO before me this 30th day of August, 1978

Elsie Willison  
Elsie Willison - Notary Public.

My commission expires July 25, 1982



KANSAS DRILLERS LOG

COMPANY Zorger Oil Company

SEC. 20 T. 29S R. 6W  
LOC. 100' N of C-SW SW

FARM McCormick NO. 1

COUNTY Kingman

ROTARY TOTAL DEPTH 4,154'

COMM. August 14, 1978

COMP. August 23, 1978

CONTRACTOR H-30, Inc.

ISSUED August 30, 1978

CASING

10 3/4"

8 5/8" Set at 237' cemented w/170 sxs cement

ELEVATION 1,537 K.B.

5 1/2"

4 1/2"

FIGURES INDICATE BOTTOM OF FORMATIONS

Sand	75'
Red Bed	239'
Red Bed and Shale	550'
Shale	1,056'
Shale and Lime	1,372'
Lime and Shale	4,134'
Lime	4,154'
Rotary Total Depth	4,154'

RECEIVED  
STATE CORPORATION COMMISSION  
AUG 31 1978  
CONSERVATION DIVISION  
Wichita, Kansas

I hereby certify the above and foregoing to be a true and correct log of the above described well as shown by the drilling reports.

H-30, Inc.

Dean Britting  
Dean Britting

State of Kansas }  
County of Sedgwick } ss:

Subscribed and Sworn to before me a Notary Public in and for said county and state this 30th day of August, 1978.



Elsie Willison  
Elsie Willison - Notary Public

My Commission Expires:  
July 25, 1982