


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail for Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittig Building
Wichita, Kansas

Kingman County, Sec. 24 Twp. 29S Rge. 6W (E) (W)

NORTH



Locate well correctly on above
Section Plat

Location as "NE/CNW/SW" or footage from lines SE SE SW
Lease Owner Aylward Drilling Company
Lease Name Bentley (OWWO) Well No. 1
Office Address 813 First Nat'l. Bank - Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed August 19, 1951 19
Application for plugging filed February 1 19 54
Application for plugging approved February 9 19 54
Plugging commenced January 30 19 54
Plugging completed February 2 19 54
Reason for abandonment of well or producing formation dry

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Ruell Durkee
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4620 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	92'	None
				5-1/2"	4616'	3617'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plug set at 4460'. Ran 6 sacks of cement on plug at 4460'. Cement filled to 4415'. Mudded hole to 210', set a 10' rock bridge and ran 25 sacks of cement at 200'. Mudded hole to 15' and ran 5 sacks of cement on top. Plugging completed.

RCUD 02-11-54

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor West Supply Company
Address Chase, Kansas

STATE OF Kansas COUNTY OF Sedgwick, ss.
Paul W. Hesse (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Paul W. Hesse

SUBSCRIBED AND SWORN TO before me this 10th day of February, 19 54

(Address) _____
Anna Beth Huffine
Notary Public.

My commission expires _____

24-7368-S 3-53-20M

AnnaBeth Huffine
NOTARY PUBLIC
COMMISSION EXPIRES APRIL 6, 1955

PLUGGING
FILE SEC 24 T 29 R 6W
BOOK PAGE 12 LINE 32

15-095-00181-00-01

Bentley #1
OPERATOR: Earl F. Wakefield
CONTRACTOR: Earl F. Wakefield
Comm: 7-28-51 Comp: 8-19-51

SE SE SW 24-29-6W
Kingman County, Kansas
Casing: 92' of 8 5/8"

1511KB

Elevation 1509DF

Surface	65
Cement	105
Shale & Shells	1065
Lime & Shale	1295
Shale & Shells	1455
Shale, Lime, & Sand	1549
Shale & Lime	1620
Lime & Shale	3475
Lime	3795
Lime & Shale	3882
Lime	3915
Lime & Shale	4067
Lime	4284
Lime & Shale	4444
Viola Lime	4458
Simpson Sand & Shale	4475
Lime & Shale	4481
Sand & Shale	4535
Shale & Lime	4572
Lime	4625
Total Depth	4625

PLUGGING
 FILE SEC 24 T 29 R 6W
 BOOK PAGE 12 LINE 32

RECEIVED
STATE CORPORATION COMMISSION

FEB 9 - 1954

CONTRACT DIVISION

Wichita, Kansas