

15.063.00-05.00.00

Form CP-3  
Rev. 6-26-62

14  
KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

APR 13 1964

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Operator's Full Name Tidewater Oil Company,

Complete Address: Box #157, Reece, Kansas.

Lease Name B. H. Hutton Well No. 1

Location CNE-SE Sec. 6 Twp. 14 Rge. (E) (W) 27

County Gove Total Depth 4420

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A X

Other well as hereafter indicated:     

Plugging Contractor: Knight Casing Pulling Company,

Address: Box # 405, Chase, Kansas. License No. 436

Operation Completed: Hour 6:00PM Day 7 Month 4 Year 1964

The Above well, was plugged as follows:

362' -- 8 5/8" Surface pipe, cement circulated with 300 Sx.  
4420' -- 5 1/2" Casing. Well plugged back with top perforations from 3860 to 3857'.

Sanded well back to 3850' and set 5 Sx. cement with dump bailer. Pulled 5 1/2" to 600' and circulated heavy gel mud. (Used 20 Sx. gel). Pulled 5 1/2" to 540' and displaced 20 Sx. cement thru 5 1/2". Pulled 5 1/2" to 360' and displaced 20 Sx. cement thru 5 1/2". Pulled 5 1/2", set bridge @ 35' and 10 Sx. cement to bottom of cellar. (Recovered 3130' 5 1/2" casing).

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: W. L. Nichols  
Well Plugging Supervisor

DATE 4/15/64

INV. NO. 8934-11