

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 - 155 - 20524-0000 (of this well)

Operator's Full Name H & H Production, Inc.

Complete Address Box 348, Russell, Kansas 67665

Lease Name Stiggins Well No. 1

Location C NW NW Sec. 17 Twp. 23 Rge. 9 (E) (W) X

County Reno Total Depth 3652'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Kelso Casing Pulling and Allied Cementing Co.

Address Box 176, Chase, Kansas License No. 683

Operation Completed: Hour Noon Day 4 Month October Year 1978

The above well was plugged as follows:

8 5/8" - 252' cement circulated - 5 1/2" - 3650' w/100 sacks PB-TD-3540 Perf. 3324-28
Hole Filled with sand to 3300' and cemented with 5 sacks.
Hole squeezed with 9 sacks hulls, 20 sacks gel-mud, and 85 sacks
50/50 Permiz w/70 gel added. pumped into 8 5/8" surface casing -
3009' of 5 1/2" casing recovered.

RECEIVED
STATE CORPORATION COMMISSION

I hereby certify that the above well was plugged as herein stated.

OCT 18 1978

INVOICED

10-18-78
CONSERVATION DIVISION
Wichita, Kansas

Signed: [Signature]
Well Plugging Supervisor

DATE 10-20-78

INV. NO. 8342-U