

15-095-018500000

Form CP-3
Rev. 6-26-62

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

JUL 19 1966
07-19-66

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Operator's Full Name Phillips Petroleum Company

Complete Address: Box 287, Great Bend, Kansas

Lease Name Osborn "A" Well No. # 1

Location C SW NW Sec. 19 Twp. 29 Rge. 6 (E) (W) W

County Kingman Total Depth 4175'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Knight Casing Pulling Company

Address: Box 405, Chase, Kansas License No. 436

Operation Completed: Hour 2:00PM Day 15th Month July Year 1966

The Above well was plugged as follows:

328' of 8 5/8" surface pipe, cement circulated. 4174' of 4 1/2" long string,
cemented with 100 sacks. Plug back T.D. 4136'. Top perforation 3730'. Bottom
of the hole was sanded to 3700', and cemented with 3 sacks, through the dump
bailer. 3430' of 4 1/2" long string was recovered from the hole. Hole was filled
with mud to 300', rock bridge from 300' to 290', and cemented with 25 sacks.
Hole was filled with mud to 40', rock bridge from 40' to 30', and cemented
with 10 sacks to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 7/19/66
INV. NO. 3598-W