

15-095-30262-0000

Form CP-3  
Rev. 6-26-62

KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 7 1966  
11-07-66  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Operator's Full Name Drillers Production Company, Inc.

Complete Address: 480 Fourth National Bank Bldg., Wichita, Kansas

Lease Name Sours Well No. # 1

Location C NE SW Sec. 14 Twp. 29 Rge. 6 (E) (W) W

County Kingman Total Depth 4520'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated: \_\_\_\_\_

Plugging Contractor: Tom-Kat Drilling, Inc.

Address: 1127 Wichita Plaza Bldg., Wichita, Kansas License No. \_\_\_\_\_

Operation Completed: Hour 4:00AM Day 5th Month Nov. Year 1966

The Above well was plugged as follows:

230' of 8 5/8" surface pipe, cement circulated with 225 sacks. Hole  
was filled with drilling mud to 225', 1st cementing plug, bridged with  
2 sacks of cement and 1/2 sack of hulls on fluid at 225', and cemented  
with 23 sacks. Hole was filled with drilling mud to 40', 2nd cementing  
plug, bridged with 1 sack of dry cement and 1/2 sack of hulls on fluid  
at 40', and cemented with 9 sacks to the base of the cellar. Rat hole  
bridged and cemented with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Audrie Elving  
Well Plugging Supervisor

DATE 11/8/66  
INV. NO. 4245-u