

15-185-20433-0000

WELL PLUGGING RECORD

Give All Information Completely  
 Make Required Affidavit

COUNTY Reno SEC. 5 TWP. 23s RGE. 9w E/W  
 Location as in quarters or footage from lines:  
SE SE


Locate Well  
 correctly on above  
 Section Platt.

Lease Owner H & H Production, Inc. purchased by Kelso Casing Pulling  
 Lease Name Wright #1 Well No. \_\_\_\_\_  
 Office Address Box 348, Russell, Kansas 67665  
 Character of Well (Completed as Oil, Gas or Dry Hole): \_\_\_\_\_  
 Date Well Completed \_\_\_\_\_  
 Application for plugging filed \_\_\_\_\_  
 Plugging commenced 6/3/83  
 Plugging completed 6/7/83  
 Reason for abandonment of well or producing formation \_\_\_\_\_

Depleted

Was permission obtained from the Conservation Division or it's  
 Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Ron Wilson  
 Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom \_\_\_\_\_ T.D. 3650'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8 5/8	250'	none
				4 1/2"	3649'	2539'

Describe in detail the manner in which the well was plugged, indicating where the mud  
 fluid was placed and the method or methods used in introducing it into the hold. If cement  
 or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet  
 to \_\_\_\_\_ feet for each plug set.

Plugged off bottom with sand to 3450' & 4 sacks cement. Shot casing at 3028' 2812',  
 2683', & 2551'. Pulled 76 joints of casing. Plugged well with 4 hulls, 6 gel,  
 8 5/8" plug, & 110 sacks common cement 3% c.c.

Plugging complete.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Kelso Casing Pulling

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (employee of owner) or (owner or operator) of the  
 above-described well, being first duly sworn on oath, says: That I have knowledge of the  
 facts, statements, and matters herein contained and the log of the above-described well as  
 filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso  
Box 347, Chase, Ks. 67524  
 (Address)

SUBSCRIBED AND SWORN TO before me this 10th day of June 19 83

My Commission expires:



Irene Hoover  
 Notary Public.

EMPHASIS OIL OPERATIONS

P. O. Box 506

Russell, Kansas 67665

DRILLERS LOG

15-155-20433-0000

OPERATOR: H & H Production, Inc.  
Wendell Acres  
Russell, Kansas 67665

CONTRACTOR: Emphasis Oil Operations  
P. O. Box 506  
Russell, Kansas 67665

LEASE: Wright

WELL: #1

LOCATION: SE SE  
Section 5-23S-9W  
Reno County, Kansas

Total Depth: 3650'

Elevation: 1737' K.B.

Commenced: 6-27-77

Completed: 7-7-77

Casing: 8-5/8" @ 211'  
4-1/2" @ 3649'

Status: Oil Well

DEPTHS & FORMATIONS

(All measurements from K.B.)

Dry Sand	40	Lime & Shale	2961
Shale	1382	Lime	3045
Shale & Lime	1490	Lime & Shale	3567
Lime & Shale	2382	Lime & Chirt	3595
Shale & Lime	2707	Lime & Shale	3632
Lime	2840	Lime (R.T.D.)	3650

STATE OF KANSAS )  
COUNTY OF RUSSELL) ss

I, Joe K. Branum, of Emphasis Oil Operations, state that the above and foregoing is a true and correct log of the above captioned location.

ORIGINAL SIGNED BY  
JOE K. BRANUM

\_\_\_\_\_  
Joe K. Branum

Subscribed and sworn to before me this 13th day of July, 1977.

My Commission Expires: October 2, 1979.

\_\_\_\_\_  
Notary Public

RECEIVED  
STATE CORPORATION COMMISSION

JUN 01 1983

CONCESSION DIVISION  
Wichita, Kansas