

OCT 13 1982 15-155-20520-000

CONSERVATION DIVISION
 Wichita, Kansas

WELL PLUGGING RECORD

Give All Information Completely
 Make Required Affidavit

COUNTY Reno SEC. 4 TWP 23 RGE. 9W E/W
 Location as in quarters or footage from lines:
C SW NW

Locate Well
 correctly on above
 Section Platt.

Lease Owner H & H Supply, Inc.
 Lease Name Hester #1 Well No. _____
 Office Address Box 348 Russell, Kansas 67665
 Character of Well (Completed as Oil, Gas or Dry Hole): _____
 Date Well Completed _____
 Application for plugging filed _____
 Plugging commenced 10-1-82
 Plugging completed 10-8-82
 Reason for abandonment of well or producing formation _____
Depleted
 Was permission obtained from the Conservation Division or it's
 Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Maurice Leslie
 Producing formation _____ Depth to top _____ bottom _____ T.D. 3670'
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8-5/8"	217'	none
				5-1/2"	3636'	2514'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged off bottom with sand to 3400' and ran 5 sacks cement. Shot casing @3130', 2727' and 2528'. Pulled a total of 74 joints of 5-1/2" casing. Plugged well with 10 sacks gel, 6 sacks hulls, 15 sacks gel, 8-5/8" plug and 125 sacks 50/50 pos, 4% gel, 3% cc.

Plugging Complete.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Kelso Casing Pulling

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso
Box 347 Chase, Kansas 67524
 (Address)

SUBSCRIBED AND SWORN TO before me this 11th day of October, 1982

My Commission expires:



Irene Hoover
 Notary Public.