

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 129-20,941-0000

LEASE NAME Williams

WELL NUMBER 9-2

4180 Ft. from S Section Line

760 Ft. from E Section Line

SEC. 9 TWP. 31S RGE. 40 (E) or (W)

COUNTY Morton

Date Well Completed 1-4-89

Plugging Commenced 12-29-88

Plugging Completed 1-4-89

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR J. M. Huber Corporation

ADDRESS 7120 I-40 West, Suite 232, Amar., Tx. 79106

PHONE# (806) 353-9837 OPERATORS LICENSE NO. 5703

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC District Office prior to plugging this well? Yes

Which KCC Office did you notify? Dodge City, Kansas (Richard Lacey)

Is ACO-1 filed? Yes-Attached if not, is well log attached?

Producing Formation N/A Depth to Top N/A Bottom N/A T.D. 5500'

Show depth and thickness of all water, oil and gas formations.

2-13-89

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Morrow	Water	5104'	5108'	8-5/8"	1678'	-0-
Morrow	Water	5380'	5396'	5-1/2"	5499'	2850'

RECEIVED
 STATE CORPORATION COMMISSION
 FEB 13 1989

Describe in detail the manner in which the well was plugged, indicating where the mud was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Plug #1 CIBP at 5350', top w/20' cmt; Plug #2 CIBP at 5050' w/20' cmt cap; Plug #3 100 sx from 2350-2250'; Plug #4 50 sx from 1728-1628'; Plug #5 50 sx from 700-600'; Plug #6 10 sx from 40-0', Mud up between plugs w/19.5# mud

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor J. W. Gibson Well Service License No. 5866

Address 7400 E. Orchard Road #370, Englewood Colorado

STATE OF Texas COUNTY OF Potter, ss.

Robert R. Glenn (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]
 (Address) Robert R. Glenn
7120 I-40 West, Amarillo, Texas 79106

SUBSCRIBED AND SWORN TO before me this 9th day of February, 1989

Deniese L. Barnett Notary Public

Commission Expires: 6-26-89



INVOICE
 DATE 2-14-89
 BILL NO. 2395