

State of Kansas



15.063.00/05.00.00

FORM - CP-2
Rev. 6-26-62

JOHN ANDERSON, Jr. Governor
WILLIAM L. MITCHELL, Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

APR 13 1964

4-13-64

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Dear Sir:

Mr. Charley Goodspeed of Knight Casing Pulling Co. has this

date requested permission to plug the following described well:
Tidewater Oil Co.

Mr. Goodspeed guarantees payment of the plugging fee.

Operator's full Name: Tidewater Oil Company,

Complete Address: Box #157, Reece, Kansas.

Lease Name: B. H. Horton Well No. 1

Location: CNE-SE Sec. 6 Twp. 14 Rge. (E) (W) 27

County Gove Total Depth 4420 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Goodspeed was instructed to plug the well as follows:

362'--8 5/8" Surface pipe, cement circulated with 300 Sx.
4420'--5 1/2" casing. Well plugged back to 3860. Top perforations
from 3860 to 3857.

Sand well back to 3850 and set 5 Sx cement with dump bailer.
Pull 5 1/2" casing to 600' and circulate heavy gel mud. Pull 5 1/2"
to 540' and displace 20 Sx. cement thru 5 1/2". Pull 5 1/2" to 360'
and displace 20 Sx. cement thru 5 1/2". Pull 5 1/2". Set bridge @
35' and 10 Sx. cement to bottom of cellar.

Very truly yours,

W. L. Nichols