

State of Kansas



WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JOHN C. WOELK Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

15.063.30007.00.00

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

AUG 9 - 1965

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. "Red" Bishop of Leben Drilling, Inc. has this

date requested permission to plug the following described well:

Morrison Producing & McClure Oil Co.

Mr. Bishop guarantees payment of the plugging fee.

Operator's full Name: Morrison Producing and McClure Oil Company,

Complete Address: Box #712 Eldorado, Kansas.

Lease Name: Albin Well No. 1

Location: CSW-SW Sec. 34 Twp. 14 Rge. (E)(W) 26

County Gove Total Depth 4330 Oil Well

Gas Well Input Well SWD Well D & A  Lost Hole

Mr. Bishop was instructed to plug the well as follows:

109' -- 8 5/8" surface pipe cemented with 100 Sx. -- cement did not circulate. Ran 70 Sx. cement from top of hole through 1" pipe.

Circulate hole with heavy mud, set plug @ 540' and 20 Sx. cement.

" " 125' and 20 Sx. cement.

" " 40' with 1/2 sk. hulls & 10 sx. cement.

Very truly yours,

*N. L. Nichols*  
Conservation Division Agent