

State of Kansas



15.063.00106.00.00

FORM - CP-2
Rev. 6-26-62

JOHN ANDERSON, Jr. Governor
WILLIAM L. MITCHELL, Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

FEB 3 1964

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

CONSERVATION DIVISION
Wichita, Kansas

Dear Sir:

Mr. Glenn Hall of Knight Casing Pulling Co. has this date requested permission to plug the following described well:
Terrell Drilling & Producing
Mr. Hall guarantees payment of the plugging fee.

Operator's full Name: Terrell Drilling & Producing,

Complete Address: 754 E. Wichita, Russell, Kansas.

Lease Name: Weiland Well No. 1

Location: CNE-NE Sec. 20 Twp. 11 Rge. XX (E) (W) 31

County Gove Total Depth 4652 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Hall was instructed to plug the well as follows:

256' -- 8 5/8" Surface pipe, cement circulated with 175 Sx.

4651' -- 4 1/2" Production pipe cemented with 100 Sx.

Well plugged back to 4445'. Top perforations @ 4429.

Sand well back to 4420' and set 3 Sx. cement with dump bailer.

Pull 4 1/2" to 600', circulate heavy gel mud and displace 20 Sx. cement thru 4 1/2". Pull 4 1/2" to 250' and displace 20 Sx. cement thru 4 1/2".

Pull 4 1/2", set bridge @ 30' and 10 Sx. cement to bottom of cellar.

Very truly yours,

M. L. Nichols