

State of Kansas



15-095-20009-0000

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
FEB 27 1967
02-27-67
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Intent to Drill, filed
February 13, 1967.

Dear Sir:

Mr. Joe Gerritzen of Braden Drilling Company has this
date requested permission to plug the following described well:

Mr. Gerritzen guarantees payment of the plugging fee.

Operator's full Name: Lee Phillips Oil Co. & Braden Drilling Co.

Complete Address: 1532 Wichita Plaza Bldg., Wichita, Kansas

Lease Name: Shipley Well No. # 1

Location: C SE NW Sec. 22 Twp. 29 Rge. 6 (E)(W) W

County Kingman Total Depth 4566' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Gerritzen was instructed to plug the well as follows:

288' of 8 5/8" surface pipe, cement circulated with 250 sacks. Fill
hole with drilling mud to 260', 1st cementing plug, bridge with 1/2 sack
of hulls, and cement with 25 sacks. Fill hole with drilling mud to 40',
2nd cementing plug, bridge with 1/2 sack of hulls, and cement with 10
sacks to base of the cellar. Bridge and cement rat hole with 2 sacks.

Very truly yours,

Aubie Elving
Conservation Division Agent