

State of Kansas



FORM - CP-2

Rev. 9-8-64

15-095-30262-0000

WM. H. AVERY Governor
 WILLIAM L. MITCHELL Chairman
 JAMES O. GREENLEAF Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION
 NOV 7 1966
 11-07-66
 CONSERVATION DIVISION
 Wichita, Kansas

J. P. Roberts
 Administrator
 500 Insurance Building
 Wichita 2, Kansas

Dear Sir:

Mr. Bill Orr of Tom-Kat, Inc. has this date requested permission to plug the following described well:

Mr. Orr guarantees payment of the plugging fee.

Operator's full Name: Drillers Production Company, Inc.

Complete Address: 480 Fourth National Bank Bldg., Wichita, Ks.

Lease Name: Sours Well No. # 1

Location: C NE SW Sec. 14 Twp. 29 Rge. 6 (E)(W) W

County Kingman Total Depth 4520' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Orr was instructed to plug the well as follows:

230' of 8 5/8" surface pipe, cement circulated with 225 sacks. Fill hole with drilling mud to 225', 1st cementing plug, bridge with 1/2 sack of hulls, and cement with 25 sacks. Fill hole with drilling mud to 40', 2nd cementing plug, bridge with 1/2 sack of hulls, and cement with 10 sacks to base of the cellar. Bridge and cement rat hole with 2 sacks.

Very truly yours,

Archie Elving
 Conservation Division Agent