

15095-01000-0000

State of Kansas

FORM - CP-2  
Rev. 6-26-62



JOHN ANDERSON, Jr. Governor  
RICHARD C. BYRD Chairman  
ALVIN F. GRAUERHOLZ Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

JUN 17 1963

J. P. Roberts  
Assistant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

CONSERVATION DIVISION  
Wichita, Kansas

Dear Sir:

Mr. Earl Rowe of Stelbar Oil Corp. Inc. has this date requested permission to plug the following described well:

Mr. Rowe guarantees payment of the plugging fee.

Operator's full Name: Stelbar Oil Corporation Inc.

Complete Address: 310 Petroleum Bldg., Wichita, Kansas

Lease Name: Ravenstein Well No. # 1

Location: C SE ~~NW~~ NE Sec. 15 Twp. 29 Rge. 6 (E) (W) W

County Kingman Total Depth 4610 Oil Well         

Gas Well          Input Well          SWD Well          D & A X Lost Hole         

Mr. Rowe was instructed to plug the well as follows:

224' of 8 5/8" surface pipe, cemented with 200 sacks.  
Fill hole with mud to 240', 1st cementing plug, 1/4 sack  
hulls, cement with 20 sacks. Fill hole with mud to 40',  
2nd cementing plug, 1/4 sack hulls, cement with 8 sacks, to  
base cellar. Bridge and cement rat hole with 2 sacks.

Very truly yours,

Ardice Elving  
Conservation Division Agent