



JOHN ANDERSON, Jr. Governor
RICHARD C. BYRD Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

April 26, 1963

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION

APR 30 1963

CONSERVATION DIVISION
Wichita, Kansas

Dear Sir:

Mr. Pat Plouffe of Blackstone Drilling, Inc. has this date requested permission to plug the following described well:

Mr. Plouffe guarantees payment of the plugging fee.

Operator's full Name: Olympic Petroleum Company

Complete Address: 204 Columbia Bldg., Tulsa, Oklahoma

Lease Name: Shuff Well No. 1

Location: C NE NW Sec. 34 Twp. 23 Rge. 9 (E) (W) X

County Reno Total Depth 3820' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Plouffe was instructed to plug the well as follows:

Circulate heavy mud. Fill hole with mud to 225'. Set
rock bridge from 225' to 215' and cement with 20 sacks
through drill pipe. Fill hole with mud to 35'. Push
plug and 1/4 sack hulls to 35' and cap hole with 10 sacks
cement. Bridge, and cement rathole with 2 sacks.

Very truly yours,

[Signature]
Conservation Division Agent