

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

245 North Water
WICHITA, KANSAS 67202

May 4, 1977

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

15-155-20405-0000

RECEIVED
STATE CORPORATION COMMISSION

MAY 06 1977

CONSERVATION DIVISION
Wichita, KansasJ. Lewis Brock
Administrator
245 North Water
Wichita, Kansas 67202

Dear Sir:

Mr. Wayne Dobbs of LD Drilling Co. has this

date requested permission to plug the following described well:

Mr. Dobbs guarantees payment of the plugging fee.Operator's full Name: National Crude, Inc.Complete Address: 7701 E. Kellogg, Suite 540, Wichita, KansasLease Name: Anderson Well No. 1Location: SW SE SW Sec. 27 Twp. 23 Rge. 9 (E)(W) XCounty: Reno Total Depth 3826' Oil Well Gas Well Input Well SWD Well D & A X Lost Hole Mr. Dobbs was instructed to plug the well as follows:Fill hole with mud. Pump 40 sacks cement through drill pipeat 500'. Pump 25 sacks cement through drill pipe at 200'.Push plug and 1/2 sack hulls to 40' and cap hole with 10 sackscement. Bridge rathole and cement with 2 sacks cement.

Very truly yours,

 Conservation Division Agent