

State of Kansas



15.083-20098-0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

NOV 21 1969

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Cook of KWB has this

date requested permission to plug the following described well:

Mr. Cook guarantees payment of the plugging fee.

Operator's full Name: KWB Oil Property Management Inc.

Complete Address: 1125 Nat'l Bank of Tulsa Bldg., Tulsa, Oklahoma

Lease Name: Vernon Oliphant Well No. 1

Location: SE NE Sec. 19 Twp. 24 Rge. 23 (E) (W)

County Hodgeman Total Depth 4850' Oil Well X

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Cook was instructed to plug the well as follows:

8 5/8" to 248' circulated w/ cement. Mud 4850' to 800'

Spot 80 sacks cement 800' to 500' Mud 500' to 250'

Spot 30 sacks cement 250' to 150'. Mud 150' to 45'

Plug, ~~Hulls~~ & 15 sacks cement 45' to 0'.

Very truly yours,

Edgar J. Eves
Conservation Division Agent