



15-095-01282-0000

JOHN ANDERSON, Jr. Governor
RICHARD C. BYRD Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

REP 11-14-67

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Nov. 14, 1967.

Dear Sir:

Mr. Wilbur Crandell of Knight Caseing Pulling Co. has this date requested permission to plug the following described well:

Mr. Crandell guarantees payment of the plugging fee.

Operator's full Name: Drillers Production Co. Inc.

Complete Address: 480 4th National Bank Bldg. Wichita, Kansas
67202

Lease Name: Voran B Well No. #1W

Location: CSW-SE Sec. 27 Twp. 29 Rge. 7W (E) (W) W

County Kingman Total Depth 3293 Oil Well

Gas Well Input Well SWD Well X D & A Lost Hole

Mr. Crandell was instructed to plug the well as follows:

256 ft. of 8 5/8" surface pipe. 3230 ft. of 5 1/2" long string.
sand to 3200 ft. & 5 sacks cement. Mud to 200 ft., 10 ft.
rock bridge. 25 sacks cement. Mud to 40 ft. 10 ft. rock
bridge & 10 sacks cement to base of cellar.

Very truly yours,

Herman J. Gustafson
Conservation Division Agent