

State of Kansas



15-093-00378-0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
NOV 4 1966
11-04-66
CONSERVATION DIVISION
WICHITA, KANSAS

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Holmstrom of K.N.N.G. has this

date requested permission to plug the following described well:

Mr. Holmstrom guarantees payment of the plugging fee.

Operator's full Name: Kansas Nebraska Natural Gas Co., Inc.

Complete Address: Box 608, Hastings, Nebraska

Lease Name: Turner Well No. 1

Location: App. Center Sec. 28 Twp. 24 Rge. 38 (E)(W) XX

County Kearny Total Depth 2650' Oil Well

Gas Well X Input Well SWD Well D & A X Lost Hole

Mr. Holmstrom was instructed to plug the well as follows:

10 3/4" to 402' circulated w/ cement. 7" to 2643' circulated w/ cement.

Top Perforations 2404' Plug bottom w/ 30 sacks cement

Top of cement 2090' Mud 2090' to 500'

Spotted 20 sacks cement 500' to 400' Mud 400' to 50'

Plug, Hulls & 10 sacks cement 50' to 0'.

Very truly yours,

Edmund J. Eves
Conservation Division Agent