



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

November 9, 1970

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
NOV 18 1970
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Ralph Comstock of Comstock Pipe Pulling, Inc. has this date requested permission to plug the following described well:

Mr. Comstock guarantees payment of the plugging fee.

Operator's full Name: Oasis Petroleum, Inc.

Complete Address: 800 Sutton Place, Wichita, Kansas 67202

Lease Name: Smisor Well No. 6

Location: SE NE SW Sec. 23 Twp. 20 Rge. 9 (W) X

County: Rice Total Depth 3372' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Comstock was instructed to plug the well as follows:

Fill hole with sand to 3350' and cement with 5 sacks cement.

Bail hole to 280'. Set rock bridge from 280' to 270' and cement hole

to base of cellar with 4 yards ready-mix concrete.

Very truly yours,

Conservation Division Agent