



15-159-35587-0000

WM. H. AVERY Governor  
 WILLIAM L. MITCHELL Chairman  
 JOHN C. WOELK Commissioner  
 HARRY G. WILES Commissioner  
 RAYMOND B. HARVEY Secretary  
 E. EDWARD JOHNSON Gen. Counsel

# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)  
 500 Insurance Bldg. 212 N. Market  
 WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
 (To Be Filed By Plugging Agent)

RECEIVED  
 JULY 25, 1966  
 CORPORATION COMMISSION

AUG 1 1966  
 08-01-66  
 CONSERVATION DIVISION  
 Wichita, Kansas

J. P. Roberts  
 Administrator  
 500 Insurance Building  
 Wichita 2, Kansas

Dear Sir:

Mr. Noel Knight of Knight Casing Pulling Co. has this date requested permission to plug the following described well:

Mr. Knight guarantees payment of the plugging fee.

Operator's full Name: Clinton Oil Company

Complete Address: 6810 W. Highway 54, Wichita, Kansas

Lease Name: Rolfs Well No. 3

Location: SW SE NW Sec. 23 Twp. 20 Rge. 9 (E)(W) X

County Rice Total Depth 3384' Oil Well X

Gas Well      Input Well      SWD Well      D & A      Lost Hole     

Mr. Knight was instructed to plug the well as follows:


Fill hole with sand to 3370' and cement with 5 sacks.

Fill hole with mud to 190'. Set rock bridge from 190' to 180' and

cement hole with 25 sacks. Fill hole with mud to 30'. Set rock bridge

from 30' to 20' and cap hole with 10 sacks cement.

Very truly yours,

  
 Conservation Division Agent